### **RUN-ON AND RUN-OFF CONTROL SYSTEM PLAN**

### NEW CASTLE STATION ASH LANDFILL WEST PITTSBURG, LAWRENCE COUNTY, PENNSYLVANIA

**Prepared for:** 



### NRG POWER MIDWEST LP NEW CASTLE GENERATING STATION 2189 STATE ROUTE 168 SOUTH WEST PITTSBURG, PENNSYLVANIA 16160

**Prepared by:** 



### CIVIL & ENVIRONMENTAL CONSULTANTS, INC. 333 BALDWIN ROAD PITTSBURGH, PA 15205

CEC Project 154-531.0002

October 2016



Civil & Environmental Consultants, Inc.

### TABLE OF CONTENTS

1.0	Purpo	5e	1			
2.0	Background					
3.0	Compliance with §257.81 – Run-on and Run-off Controls for CCR Landfills					
	(Run-on and Run-off Control System Plan)					
4.0	Run-o	n Control Plan – §257.81(a)(1)	3			
5.0	Run-o	ff Control Plan - §257.81(a)(2)	3			
	5.1	Benches	4			
	5.2	Surface Water Diversion Berm	4			
	5.3	Downchutes	5			
	5.4	Channels	5			
	5.5	Culverts	5			
	5.6	Sedimentation Pond	6			
6.0	Surfac	e Water Discharge Requirements - §257.81(b)	6			
7.0	Conclu	ision	6			
8.0	0 References					

### APPENDICES

Appendix A - Professional Engineer Certification Statement

Appendix B – Drawings Site Location Map PADEP Plan and Detail Drawings Title Sheet D-728-1012 Erosion and Sedimentation Control Plan (Landfill Cover Grade – Alternate 6A) D-728-1020 Liner System/Final Cover System Details (Sheet 2 of 3) D-728-1021 Liner System/Final Cover System Details (Sheet 3 of 3) D-728-1025 Surface Water Management System Details (Sheet 1 of 4) D-728-1026 Surface Water Management System Details (Sheet 2 of 4) D-728-1027 Surface Water Management System Details (Sheet 3 of 4) D-728-1028 Surface Water Management System Details (Sheet 4 of 4)

Appendix C – PADEP Form I: Soil Erosion and Sedimentation Controls

### RUN-ON AND RUN-OFF CONTROL SYSTEM PLAN NEW CASTLE STATION ASH LANDFILL

### 1.0 PURPOSE

On behalf of NRG Power Midwest LP (NRG), Civil & Environmental Consultants, Inc. (CEC) has prepared a Run-on and Run-off Control System Plan for the New Castle Station Ash Landfill in accordance with the United States Environmental Protection Agency (USEPA) Coal Combustion Residuals (CCR) Rule 40 CFR 257.81 (§257.81) dated April 17, 2015.

A Run-on and Run-off Control System Plan must be prepared to document that the run-on and run-off control systems at the CCR landfill have been designed and implemented to meet the requirements of the CCR Rule. Each plan must be supported by appropriate engineering calculations. For existing CCR landfills, the plan must be prepared no later than October 17, 2016 and placed in the facility's operating record. The owner or operator of the CCR unit must obtain a written certification from a qualified professional engineer that the design meets the requirements of this section. The professional engineer certification is provided in Appendix A.

### 2.0 BACKGROUND

New Castle Station Ash Landfill (Landfill) is located in West Pittsburg, Lawrence County, Pennsylvania. Refer to Figure 1 in Appendix B for the Site Location Map. The Landfill operates under Pennsylvania Department of Environmental Protection (PADEP) Solid Waste Permit No. 300818 issued April 23, 2008. The Landfill is a captive residual waste disposal facility that receives CCR from New Castle Generating Station (Station) and sediments from the ponds at the site (residual wastes). The Station ceased using coal to generate power on March 23, 2016. Disposal of residual wastes at the Landfill is anticipated to continue through the Station's estimated shutdown date in the mid-2030s. The Landfill has a stormwater management system permitted under PADEP Solid Waste Permit No. 300818 that is designed and constructed to control run-on and run-off. The stormwater outfall for the landfill is permitted under National Pollutant Discharge Elimination System (NPDES) Permit No. PA0005061. A Major Permit Modification (MPM) Application to Solid Waste Permit No. 300818 was submitted to PADEP in December 2010 and approved on June 9, 2011. The MPM Application included proposed filling alternates for Stages 4, 5, and 6 of the Landfill over Stages 1, 2, and 3. The MPM Application included filling of Stage 4 over a liner/leachate collection system, installation of a final cover system for Stage 5, and either installation of a final cover system (Alternate 6A) or filling (Alternate 6B) of Stage 6. The MPM Application included design of stormwater controls for both alternates. In Stages 5 and 6, a final cover system was installed (Alternate 6A). A final cover system was also installed over portions of Stages 1, 2, and 3 that were not overlain by Stages 4, 5, and 6. Permanent stormwater controls were installed in these areas in general accordance with the Erosion and Sedimentation Control Plan for Alternate 6A that was included in the MPM Application.

The final cover system will be installed over Stage 4 after filling is complete. Permanent stormwater controls will be installed in these areas in general accordance with the Erosion and Sedimentation Control Plan for Alternate 6A, with some possible variations based on the final grades reached during filling.

The drawing showing the Erosion and Sedimentation Control Plan for Alternate 6A and drawings showing details are included in Appendix B.

### 3.0 COMPLIANCE WITH §257.81 – RUN-ON AND RUN-OFF CONTROLS FOR CCR LANDFILLS

\$257.81 establishes requirements for run-on and run-off system controls for existing and new CCR landfills and requires the owner or operator to design, construct, operate and maintain:

§257.81(a)(1) A run-on control system to prevent flow onto the active portion of the CCR unit during the peak discharge from a 24-hour, 25-year storm; and§258.81(a)(2) A run-off control system from the active portion of the CCR unit to collect and control at least the water volume resulting from a 24-hour, 25-year storm.

Civil & Environmental Consultants, Inc.

In addition, §257.81(b) requires that run-off from the active portion of the CCR unit must be handled in accordance with the surface water requirements under §257.3-3 which relate to water quality standards for discharges of surface water.

The following sections address the information required by §257.81. This Run-On and Run-Off Control System Plan is consistent with the PADEP Form I: Soil Erosion and Sedimentation Controls dated December 2010. The approved Form I is provided in Appendix C.

### 4.0 **RUN-ON CONTROL PLAN - §257.81(a)(1)**

The stormwater run-on control system prevents flow from entering onto the active portion of the CCR unit. The run-on control system includes the perimeter berm that has been constructed on all sides of Stage 4 where filling is occurring (the active portion of the landfill). The perimeter berm is constructed of CCR from the site, and has intermediate cover on the outer slope.

The perimeter berm limits run-on from adjacent areas. Flow outside of the perimeter berm over the intermediate cover is collected as run-off and discharged to a sedimentation pond. Within the perimeter berm, CCR are generally placed in horizontal lifts. The CCR are graded to direct flow to a vertical riser at the center of the Stage which discharges through the landfill and is treated as leachate, and is ultimately conveyed to a leachate pond.

As filling progresses, the perimeter berm is built up to maintain a height of approximately 4-feet. Outside of the perimeter berm, the slopes grade away from the active portion of the landfill at approximate 3H:1V slopes. With this configuration, there is no accumulation of surface water near the berm; all flow is directed away from the berm. The 4-feet high berm is therefore a sufficient run-on control for the 24-hour, 25-year storm event.

### 5.0 **RUN-OFF CONTROL PLAN - §257.81(a)(2)**

The Landfill has a stormwater management system permitted under PADEP Solid Waste Permit No. 300818 that is designed and constructed to control run-off from the final slopes of the landfill. The stormwater run-off control system includes benches, downchutes, channels, culverts, and the sedimentation pond. The MPM Application Form I provides the design calculations for the stormwater control system. The design calculations were completed in accordance with the PADEP Bureau of Soil and Water Conservation, Erosion and Sediment Pollution Control Manual, dated April 2000. The stormwater design includes benches, diversion berms, downchutes, channels, and culverts. This run-off control plan addresses the stormwater control system for Alternative 6A. Permanent stormwater controls will be installed in these areas in general accordance with the Erosion and Sedimentation Control Plan for Alternate 6A, with some possible variations based on the final grades reached during filling. If needed, a revised Erosion and Sedimentation Control Plan will be prepared based on the final grades reached during filling.

### 5.1 BENCHES

The benches of the Landfill are graded into the waste and final cover system. The final cover grading includes 3H:1V final grades with 15-feet wide benches spaced approximately every 25 feet vertically. The benches are sloped inward towards the landfill at approximate 5 percent slopes as shown on the details included on the drawings in Appendix B. The benches receive run-off from the 3H:1V final grades of the landfill and are sloped to convey the run-off to downchutes. The benches are designed to convey flow from the 25-year, 24-hour storm event. A calculation for benches was performed and is included in Appendix C with the Form I calculations.

### 5.2 SURFACE WATER DIVERSION BERM

Surface water diversion berms are used to convey runoff from the Landfill to downchutes. The diversion berms are generally used on slopes that are more shallow than 3H:1V. The height of the diversion berms vary. The diversion berms are designed to convey flow from the 25-year, 24-hour storm event.

### Civil & Environmental Consultants, Inc.

### 5.3 **DOWNCHUTES**

Downchutes at the site generally convey run-off off down the 3H:1V slopes of the Landfill to perimeter channels. Downchutes are also used on shallower slopes to convey run-off to perimeter channels. The downchutes are typically trapezoidal as shown on the details included on the drawings in Appendix B. The downchutes are lined with concrete revetment due to the steepness of the slopes. The downchutes are designed to convey flow from the 25-year, 24-hour storm event. The downchutes convey run-off to perimeter channels. At the discharge point of each downchute, the concrete revetment mat extends into the perimeter channels.

### 5.4 CHANNELS

Channels at the site generally convey run-off around the perimeter of the Landfill through culverts as needed and ultimately to the sedimentation pond. The channels are typically trapezoidal, as shown on the details included on the drawings in Appendix B. The channels are either grass-lined, lined with R-4 riprap, or lined with concrete revetment. The lining of the channels depends on the slope of the channel and the flow through the channel during the 25-year, 24-hour storm event. The channels are designed to convey flow from the 25-year, 24-hour storm event.

### 5.5 CULVERTS

The culverts convey run-off between channel segments. Typically, culverts are used at road crossings. Drop inlet boxes are used to inlet flow from the perimeter channel segments into the culverts. The culverts are designed to be HDPE or concrete. The culverts are designed to convey flow from the 25-year, 24-hour storm event.

Civil & Environmental Consultants, Inc.

### 5.6 SEDIMENTATION POND

The existing sedimentation pond includes a principal and emergency spillway. The existing sedimentation pond has capacity for the 25-year, 24-hour storm event. The stormwater outfall from the sedimentation pond is permitted under NPDES Permit No. PA0005061 as outfall 006. The sedimentation pond discharges to the Beaver River.

### 6.0 SURFACE WATER DISCHARGE REQUIREMENTS - §257.81(b)

§257.81(b) requires that run-off from the active portion of the CCR unit must be handled in accordance with the surface water requirements under §257.3-3 which relate to water quality standards for discharges of surface water. In accordance with §257.3-3, discharges from the sedimentation pond are authorized by and in compliance with PADEP under NPDES Permit No. PA0005061. Dredged material or fill material is not discharged from the Site to waters of the United States in violation of the requirements under Section 404 of the Clean Water Act. Site operations have not caused non-point source pollution to waters of the United States in violation of the requirements under Section 208 of the Clean Water Act.

### 7.0 CONCLUSION

The Run-on and Run-off Control System Plan demonstrates that the Site is designed, constructed, operated, and maintained in accordance with Section §257.81 of the CCR Rule. The certification statement by a qualified professional engineer is provided in Appendix A. Supporting drawings and calculations are provided in Appendices B and C. This demonstration will be placed in the operating record by October 17, 2016.

### Civil & Environmental Consultants, Inc.

### 8.0 **REFERENCES**

 Application for Major Permit Modification of Vertical Expansion. New Castle Ash Landfill. Permit I.D. No. 300818. December 2010. Civil & Environmental Consultants, Inc.

### APPENDIX A

### PROFESSIONAL ENGINEER CERTIFICATION STATEMENT

### **PROFESSIONAL ENGINEER CERTIFICATION**

This Run-on and Run-off Control System Plan fulfills the CCR Rule requirements (40 CFR Parts 257 and 261) dated April 17, 2015. This Run-on and Run-off Control System Plan will be placed in the operating record by October 17, 2016.

I, Angela M. Ramirez, P.E., a registered professional engineer in the State of Pennsylvania, certify that the Run-on and Run-off Control System Plan for the New Castle Station Ash Landfill fulfills the requirements of §257.81. This certification is based on my review of the Run-on and Run-off Control System Plan for New Castle Station Ash Landfill.

Angela M. Ramirez, P.E.

Printed Name of Professional Engineer

Ungela M. Raminic Signature

PE082317

Registration No.

Pennsylvania Registration State

10-14-2016 Date

Stamp/Seal:



### **APPENDIX B**

### DRAWINGS



2010 0 4116 PERMIT DWG よいて

0.2.28



# **MAJOR PERMIT MODIFICATION** OF **VERTICAL EXPANSION**

# **STAGES 4, 5, AND 6 ORION POWER MIDWEST, L.P. - NEW CASTLE PLANT ASH LANDFILL** TAYLOR TOWNSHIP, LAWRENCE COUNTY PENNSYLVANIA

# **PREPARED FOR**



# **ORION POWER MIDWEST, L.P. NEW CASTLE GENERATION STATION ROUTE 168** WEST PITTSBURG, PENNSYLVANIA 16160

## **PREPARED BY**

Civil & Environmental Consultants, Inc. 333 Baldwin Road Pittsburgh, PA 15205

**PROJECT NO.: 040-654 DECEMBER 2010** 

9	10	11	12			13
				ND.	DATE	REV

		LIST OF DRAWINGS	
NEW DRAWING NO.	PREVIOUS DRAWING NO.	DRAWING TITLE	
		TITLE SHEET	
728-1001	F002	EXISTING SITE CONDITIONS & SEASONALLY HIGH GROUNDWATER CONTOURS	
728-1002	F003	1/4-MILE AND 1/2-MILE RADIUS (SHEET 1 OF 3)	
728-1003	F004	1/4-MILE AND 1/2-MILE RADIUS (SHEET 2 OF 3)	
728-1004	F005	1/4-MILE AND 1/2-MILE RADIUS (SHEET 3 OF 3)	
728-1005	F015	LANDFILL STAGING PLAN STAGE 4	
728-1006	F016	LANDFILL STAGING PLAN STAGE 5	
728-1007	F006	TOP OF SUBBASE/GRADING PLAN (ALTERNATE 6A)	T
728-1008	F007	TOP OF FINAL COVER GRADING PLAN (ALTERNATE 6A)	T
728-1009	F008	LEACHATE COLLECTION/DETECTION PIPING PLAN (ALTERNATE 6A)	T
728-1010	F009	LANDFILL CROSS-SECTIONS (ALTERNATE 6A)	T
728-1011	F017	LANDFILL STAGING PLAN STAGE 6A (ALTERNATE 6A)	T
728–1012	F020	E&S PLAN (LANDFILL BASE GRADES ALTERNATE 6A)	T
728–1013		TOP OF SUBBASE/GRADING PLAN (ALTERNATE 6B)	T
728-1014		TOP OF FINAL COVER GRADING PLAN (ALTERNATE 6B)	T
728-1015		LEACHATE COLLECTION/DETECTION PIPING PLAN (ALTERNATE 6B)	T
728-1016		LANDFILL CROSS-SECTIONS (ALTERNATE 6B)	
728-1017	F018	LANDFILL STAGING PLAN STAGE 6B (ALTERNATE 6B)	T
728-1018		E&S PLAN (LANDFILL FINAL GRADES ALTERNATE 6B)	T
728-1019	F010	LINER SYSTEM/FINAL COVER SYSTEM DETAILS (SHEET 1 OF 3)	T
728-1020	F011	LINER SYSTEM/FINAL COVER SYSTEM DETAILS (SHEET 2 OF 3)	T
728-1021	F025	LINER SYSTEM/FINAL COVER SYSTEM DETAILS (SHEET 3 OF 3)	T
728-1022	F012	LEACHATE MANAGEMENT SYSTEM DETAILS (SHEET 1 OF 3)	T
728-1023	F013	LEACHATE MANAGEMENT SYSTEM DETAILS (SHEET 2 OF 3)	T
728-1024	F014	LEACHATE MANAGEMENT SYSTEM DETAILS (SHEET 3 OF 3)	T
728-1025	F021	SURFACEWATER MANAGEMENT SYSTEM DETAILS (SHEET 1 OF 4)	╈
728-1026	F022	SURFACEWATER MANAGEMENT SYSTEM DETAILS (SHEET 2 OF 4)	T
728-1027	F023	SURFACEWATER MANAGEMENT SYSTEM DETAILS (SHEET 3 OF 4)	T
728-1028	F026	SURFACEWATER MANAGEMENT SYSTEM DETAILS (SHEET 4 OF 4)	$\uparrow$
728-1029	F024	LEACHATE POND UPGRADE AND DETAILS	$\uparrow$
VOID	F019	E&S PLAN (LANDFILL BASE GRADES)	$\uparrow$

ISION	BY CHK. APP. APP.	]
		A
		B
		C
		D
		E
PREPARED BY CEC CEC	DRAWING DATE 11/10/10 11/10/10	F
CEC CEC CEC CEC CEC CEC CEC CEC CEC CEC	$     \begin{array}{r}       11/10/10 \\       10/10 \\       10/10 \\       10/10 \\       10/10 \\       10/10 \\       10/10 \\       10/10 \\       10/10 \\  $	G
CEC CEC CEC CEC CEC CEC CEC CEC CEC CEC	11/10/10         11/10/10         11/10/10         11/10/10         11/10/10         11/10/10         11/10/10         11/10/10         11/10/10         11/10/10         11/10/10         11/10/10         11/10/10         11/10/10         11/10/10	H
CEC CEC CEC CEC CEC CEC	11/10/10 11/10/10 11/10/10 11/10/10 11/10/10 11/10/10	J
1	REGISTERED PROFESSIONAL DUANE LANDUE ENGINEER P0076388	K



2010\100-063\-CADD\DWG\TASK 0002 - PTI\DWG\RR\7281012.DWG{728-1012} (TNEWMYER) - DEC 1, 2010 - §

ISTING INDEX CONTOU ISTING INTERMEDIATE	JR CONTOUR	А
ISTING EDGE OF ROAI ISTING BUILDING	D	
ISTING STREAM OR RI ISTING TREELINE ISTING SPOT FI	IVER	
DETAIL DRAWING NUMBER		
IITS OF VERTICAL EXF AGE LIMITS	PANSION DISPOSAL AREA	
ISTING PERMIT BOUND P OF FINAL COVER II	DARY NDEX CONTOUR	В
P OF FINAL COVER II	NTERMEDIATE CONTOUR	
UL/ACCESS ROAD ORMWATER FLOW DIRE	ECTION	
		С
		П
		D
		_
		F
		F
IY PROVIDED BY AERI	AL	
CLAY PIKE, N. HUNTIN DTOGRAPHY TAKEN 1– R INTERVAL. AND FRO	NGTON, -11–07, M	
BASED ON 3-18-10	GROUND	G
		Н
	PROFESSIONAL	
	DUANE LANDUE	
00		
	* HAND SIGNATURE ON FILE	
onmental Cons	sultants, Inc.	J
24 · 800.365.2324 · Fax: 4 www.cecinc.com	412.429.2114	
NOS, 3, 4.	ANT AND 5	
AND SEDIME		
INTROL PLAT ER GRADE-A	N Alternate 6a)	
SPS T	DRAWING NUMBER	$\checkmark$
	SHEET.	
E: 30X42	FILE: 7281012.DWG	



REVISIE



9	10	11	12	13
	FINAL COVER SYST	TEM A 1020 FUTURE TIE-IN	1-FT 3-FT 1.5-FT LEXISTING ASH GEOSYNTHETIC SOIL BACKFILL	
		<u>TEMPORA</u> <u>TERMINATION</u> <u>BEI</u>	DETAIL D ARY FINAL COVER SYSTE N-AT TOP OF CLOSED SL OW STAGE 5 AND 6 N.T.S.	<u>M</u> OPES
	XXXXX ASH	ASHTO NO. 57 OR NO. 8 AGGREGATE 4" DIA. SDR-17 HDF PERFORATED PIPE O EQUIVALENT	E 1-FT B OZ NON-WOVEN GEOTEXTILE FILTER SEW GEOTEXTILE SEAM MANAGEMENT J J DE R 6'	

DETAIL E FINAL COVER SYSTEM DRAINAGE LAYER PIPE N.T.S.



RE∨ISION

ND. DATE



5	6	7	8	
_	_	·	_	

OP WIDTH (TW) (FT)	BOTTOM WIDTH (BW) (FT)	SIDE SLOPES (Z1/Z2)	FREEBOARD (FB) (FT)	LINING MATERIAL
18.0	6.0	3/3	1.0	GRASS
18.0	6.0	3/3	1.0	GRASS
14.0	6.0	2/2	1.3	GRASS
12.0	4.0	2/2	1.2	GRASS
12.0	4.0	2/2	1.3	GRASS
12.0	4.0	2/2	1.2	GRASS
16.0	4.0	3/3	1.7	GRASS
16.0	4.0	3/3	1.7	GRASS
16.0	4.0	3/3	1.2	GRASS
16.0	4.0	3/3	1.5	GRASS
16.0	4.0	3/3	1.6	GRASS
6.0	2.0	2/2	0.7	R4-RIPRAP
26.0	18.0	2/2	1.6	GRASS
12.0	4.0	2/2	1.2	GRASS
10.0	4.0	3/3	0.8	GRASS
10.0	4.0	3/3	0.7	GRASS
6.5	2.5	2/2	0.8	CONCRETE REVETMENT
8.5	2.5	2/2	1.4	CONCRETE REVETMENT
8.5	2.5	2/2	1.3	CONCRETE REVETMENT
8.5	2.5	2/2	1.4	CONCRETE REVETMENT
6.5	2.5	2/2	0.9	CONCRETE REVETMENT
5.0	1.0	2/2	0.8	CONCRETE REVETMENT
8.5	2.5	2/2	1.4	CONCRETE REVETMENT
8.5	2.5	2/2	1.3	CONCRETE REVETMENT
8.5	2.5	2/2	1.4	CONCRETE REVETMENT
6.5	2.5	2/2	0.8	CONCRETE REVETMENT
6.5	2.5	2/2	0.9	CONCRETE REVETMENT
8.5	2.5	2/2	1.4	CONCRETE REVETMENT
8.5	2.5	2/2	1.4	CONCRETE REVETMENT
8.5	2.5	2/2	1.4	CONCRETE REVETMENT

ALTERNATE 6B CHANNEL SCHEDULE												
CHANNEL	REACH	BEGIN STATION	END STATION	DETAIL	DRAWING NO.	TOTAL CHANNEL DEPTH (TD) (FT)	FLOW DEPTH (FT)	TOP WIDTH (TW) (FT)	BOTTOM WIDTH (BW) (FT)	SIDE SLOPES (Z1/Z2)	FREEBOARD (FB) (FT)	LINING MATERIAL
CHANNEL A	OUTLET	0+00	9+05	D	1025	2.0	1.2	18.0	6.0	3/3	0.8	GRASS
CHANNEL A	REACH 1	9+29	10+61	D	1025	2.0	1.2	18.0	6.0	3/3	0.8	GRASS
CHANNEL A	REACH 2	10+61	15+71	E	1025	2.0	1.1	14.0	6.0	2/2	0.9	GRASS
CHANNEL A	REACH 3	15+71	17+47	E	1025	2.0	1.1	12.0	4.0	2/2	0.9	GRASS
CHANNEL A	REACH 4	17+87	26+87	A	1025	2.0	1.0	12.0	4.0	2/2	1.0	GRASS
CHANNEL A	REACH 5	25+88	33+00	A	1025	2.0	0.8	12.0	4.0	2/2	1.2	GRASS
CHANNEL A	REACH 6	33+50	34+10	A	1025	2.0	0.3	16.0	4.0	3/3	1.7	GRASS
CHANNEL A	REACH 7	34+10	39+45	A	1025	2.0	0.3	16.0	4.0	3/3	1.7	GRASS
CHANNEL B	REACH 1	0+00	3+52	D	1025	2.0	0.8	16.0	4.0	3/3	1.2	GRASS
CHANNEL B	REACH 2	3+52	14+15	A	1025	2.0	0.5	16.0	4.0	3/3	1.5	GRASS
CHANNEL B	REACH 3	14+15	31+45	A	1025	2.0	0.5	16.0	4.0	3/3	1.5	GRASS
CHANNEI C		0+00	14+87	С	1025	1.0	0.2	6.0	2.0	2/2	0.8	R4-RIPRAP
CHANNEL D	REACH 1	0+00	1+00	A	1025	2.0	0.4	26.0	18.0	2/2	1.6	GRASS
CHANNEL D	REACH 2	1+00	9+22	A	1025	2.0	0.8	12.0	4.0	2/2	1.2	GRASS
CHANNEL F	REACH 1	0+00	4+65	F	1020	1.0	0.3	10.0	4.0	3/3	0.7	GRASS
CHANNEL F	REACH 2	4+65	5+99	G	1020	1.0	0.2	6.5	2.5	2/2	0.8	CONCRETE REVETMENT
CHANNEL G		0+00	4+03	F	1020	1.0	0.2	6.5	2.5	2/2	0.8	CONCRETE REVETMENT
DOWN CHUTE 1		0+00	1+30	В	1025	1.5	0.1	8.5	2.5	2/2	1.4	CONCRETE REVETMENT
DOWN CHUTE 2		0+00	4+79	В	1025	1.5	0.3	8.5	2.5	2/2	1.2	CONCRETE REVETMENT
DOWN CHUTE 3		0+00	1+26	В	1025	1.5	0.1	8.5	2.5	2/2	1.4	CONCRETE REVETMENT
DOWN CHUTE 4		0+00	0+82	В	1025	1.0	0.1	6.5	2.5	2/2	0.9	CONCRETE REVETMENT
DOWN CHUTE 5		0+00	1+40	В	1025	1.0	0.2	5.0	1.0	2/2	0.8	CONCRETE REVETMENT
DOWN CHUTE 6		0+00	1+25	В	1025	1.5	0.1	8.5	2.5	2/2	1.4	CONCRETE REVETMENT
DOWN CHUTE 7		0+00	2+37	В	1025	1.0	0.2	6.5	2.5	2/2	0.8	CONCRETE REVETMENT
DOWN CHUTE 8		0+00	1+60	В	1025	1.0	0.1	6.5	2.5	2/2	0.9	CONCRETE REVETMENT
DOWN CHUTE 9		0+00	0+43	В	1025	1.5	0.1	8.5	2.5	2/2	1.4	CONCRETE REVETMENT
DOWN CHUTE 11	REACH 1	0+00	1+50	В	1025	1.5	0.1	8.5	2.5	2/2	1.4	CONCRETE REVETMENT
DOWN CHUTE 11	REACH 2	1+50	3+33	В	1025	1.5	0.1	8.5	1.5	2/2	1.4	CONCRETE REVETMENT

![](_page_18_Figure_0.jpeg)

5	6	7	8	9	10	11	12	13

![](_page_19_Figure_0.jpeg)

	5	6	7	8	
				STD PLASTIC ( 3-FT X 3-FT WITH 4-IN -	COATED GABION X 6—IN FILL 8—IN STONE
				8 OZ/SY GEOTEXTILE         OR EQUAL         It         R-4 FILTER STONE         AASHTO NO. 57         FILTER STONE	
	-1-FT (TYP )				
27 27 2.) COTEXTI			6–IN PIPE	NO. 57 STONE	E RISER
	FT X 10-FT ICRETE PAD		<u>NO</u> 1. Y	TE: WHEN TOP OF ASH IS 5-FT BELOW TOP OF	
	AS	IN THICK WASTE ASH	2. / 3. F	ALL GEOTEXTILE SEAMS TO BE SEWN OR L RISER PIPE PERFORATIONS TO BE 3/4–IN 6 PER ROW BETWEEN EVERY OTHER PIPE	LEISTER <u>ED</u> . DIA. RIB. DECANT I
	-R-4 FILTER STONE				
	#57 FILTER STON	Ε			
<b>A</b>			2-FT DIA. F RISER WITH (SEE NOTES	PERFORATED N12 PIPE	
10-FT			6–IN STD PLASTIC COATE 3–FT X 3–FT X 6– WITH 4–IN – 8–IN	N PA DOT No 3 STONE ED GABION -IN FILL STONE	
6—IN (TYP.)					
			AASHTO NO. 57 FILTER STONE		
ATER. DN					
			R-4 FILTER STONE		

![](_page_19_Figure_3.jpeg)

9–FT

6-IN PA DOT No 3 STONE-

10

11

12

![](_page_19_Figure_8.jpeg)

DETAIL C

DECANT RISER STRUCTURE LATERAL EXTENSTION

N.T.S.

ND. DATE

FOR PERMIT ONLY

RE√ISION

![](_page_19_Figure_9.jpeg)

PROFESSIONAL

13			14		
					А
				-	В
					С
				-	D
				-	E
-FT (TYP.)	(INW) L				F
	TONE				G
					Н
<b>ivil &amp; En</b> 333 E Ph: 412.42	vironment Baldwin Road - F 29.2324 · 800.365 www.cec / CASTL	<b>tal Con</b> Pittsburgh, P. .2324 · Fax: - inc.com _E PL -2 /	* HAND SIGNATURE	ON FILE	J
SURFAC SURFAC ( 11/10/10 D (ED ED INE: ENG AS SHOWN	E WATE YSTEM SHEET BY. SPS DMT DRL SIZE: 30X42	3, 4, R MAN DETAI 3 OF	JAGEMENT LS 4) DRAWING NUMBER D-728-1027 SHEET: FILE: 7281027.DV	2 VG	К

![](_page_20_Figure_0.jpeg)

![](_page_20_Figure_1.jpeg)

5	6	7	8
J	0	/	0

9	10		11		12	13
			P SYSTEM			
		1021 DRAINAGE L	AYER PIPE	<u> </u>	N SDR-17 HDPE SO	LID PIPE TO BE
				EXT (SE FOF	ENDED 1-FT BEYON E DETAIL A ON DRA 2 ALIGNMENT)	D LIMIT OF REVETMENT MAT. WING D-728-1027
		ASH				
	-	10-FT				
<u>-</u>	STAGE 5 NORTH S DF	LOPE FINAL RAINAGE PIP	COVER SYSTEM	<u>CHANNEL</u>		
2-FT SOIL COVER						
				-REVETMENT LINED DOWNCHUTE CHANNEL	/── 4-IN SDR-17	HDPE SOLID PIPE TO BE
ASH	2.25-17				EXTENDED 1-F (SEE DETAIL A FOR ALIGNMEN	T BEYOND LIMIT OF REVETMENT MAT. ON DRAWING D-728-1028 T)
	DRAINAGE LAYER PIPE	<u>E</u> 028	/~2.	25-FT		
		DET	TAIL D	1		
	TYPICA	AL FINAL CO DRAINAGE	VER SYSTEM BEI PIPE OUTLET I.T.S.	<u>NCH</u>		
		A FINAL COVER	SYTEM REVETMEN DOWNCHUT	- LINED E CHANNEL		
	ASH		40-MIL TEXTURED	IDPE CAP		FOR PERMIT
	DDAINAC		EXTENDED 1-FT BEYOND (SEE DETAIL A ON DRAW FOR ALIGNMENT)	LIMIT OF REVETMENT MAT. ING D-728-1028		Civil & Envi
	DRAINAGE	<u>LAYER PIPI</u> N.T.S.	<u>E AT BENCH</u>			333 Bal Ph: 412.429.2 NEW
						Energy UNIT
						DRAWN: 11/10/10 E CHECKED T
		ΠΔΤΕ				APPROVED I APPROVED DISCIPLINE: ENG
	NU.			ВА		MUNN SOULT HO OUTWIN S

![](_page_20_Figure_6.jpeg)

### **APPENDIX C**

### PADEP FORM I

![](_page_22_Figure_0.jpeg)

### Area Listing (all nodes)

Area	CN	Description
(acres)		(subcatchment-numbers)
1.500	61	(DA-1)
1.500	61	TOTAL AREA

### Soil Listing (all nodes)

Area	Soil	Subcatchment
(acres)	Group	Numbers
0.000	HSG A	
0.000	HSG B	
0.000	HSG C	
0.000	HSG D	
1.500	Other	DA-1
1.500		TOTAL AREA

### Summary for Subcatchment DA-1: Area 1

Runoff = 2.12 cfs @ 11.96 hrs, Volume= 0.085 af, Depth> 0.68"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.01 hrs Type II 24-hr 25yr-24hr Rainfall=3.93"

![](_page_25_Figure_5.jpeg)

### Summary for Reach 1R: Bench (3H:1V slopes to bench)

![](_page_26_Figure_3.jpeg)

![](_page_27_Figure_0.jpeg)

### Area Listing (all nodes)

Area	CN	Description
(acres)		(subcatchment-numbers)
1.850	61	(DA-2)
1.850	61	TOTAL AREA

### Soil Listing (all nodes)

Area	Soil	Subcatchment
(acres)	Group	Numbers
0.000	HSG A	
0.000	HSG B	
0.000	HSG C	
0.000	HSG D	
1.850	Other	DA-2
1.850		TOTAL AREA

### Summary for Subcatchment DA-2: Area 2

Runoff = 2.03 cfs @ 12.02 hrs, Volume= 0.105 af, Depth> 0.68"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.01 hrs Type II 24-hr 25yr-24hr Rainfall=3.93"

![](_page_30_Figure_5.jpeg)

### Summary for Reach 2R: Bench (20 percent slopes to bench)

![](_page_31_Figure_3.jpeg)

## FORM I SOIL EROSION AND SEDIMENTATION CONTROLS

## FORM I SOIL EROSION AND SEDIMENTATION CONTROLS ALTERNATE 6A

2540-PM-BWM0390 6/2005

![](_page_34_Picture_1.jpeg)

### COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION BUREAU OF WASTE MANAGEMENT

Date Prepared/Revised
April 27, 2007
Rev. February 2008
Rev. November 3, 2008
Rev. December 2010
DEP USE ONLY
Date Received

### FORM I

## SOIL EROSION AND SEDIMENTATION CONTROLS

This form must be fully and accurately completed. All required information must be typed or legibly printed in the spaces provided. If additional space is necessary, identify each attached sheet as Form I, reference the item number and identify the date prepared. The "date prepared/revised" on any attached sheets needs to match the "date prepared/revised" on this page.

General References: 273.151, 275.205, 277.151, 279.232, 281.132, 283.106, 288.151, 289.252, 291.205, 293.232, 295.132, 297.106

SECTION A. SITE IDENTIFIER

Applicant/permittee: Orion Power Midwest, L.P.

Site Name: New Castle Plant Ash Landfill

Facility ID (as issued by DEP): 300818

### SECTION B. EROSION AND SEDIMENT CONTROL

Provide a plan for the control of erosion and sedimentation on land within the permit area, all borrow areas and adjacent areas to be disturbed by construction activities. Include a narrative describing the implementation of the plan, its relationship to the overall staging of earth moving activities, and detailed design and construction plans and specifications for each structure or facility used in the plan. The plan must be site specific for each phase of construction. Include design assumptions, runoff calculations, channel profiles, cross sections, channel linings, and applicable details on attached Data Sheet for all collection and interceptor ditches. Provide documentation on the capacity of existing drainage system and the effect disposal activities will have on the drainage. Show discharge points to natural drainage ways and all culverts that carry drainage away from the site. Plans and maps shall contain all details necessary for construction of the structures.

SECTION C. DIVERSION CONTROLS

Provide a plan for the collection and conveyance to a natural drainageway of the runoff from up slope undisturbed areas. Include design calculations, profiles, cross sections, and applicable details for each structure, ditch, or channel used for diverting runoff. The diversion control and erosion and sedimentation control plan shall be based on the requirements of Chapter 102 (Erosion and Sedimentation Control) of the Department's regulations. Calculations indicating water quantities shall be based on a 24-hour precipitation event with a frequency of once in 25 years. More stringent criteria may be required by the Department based on the most recent edition of the USDA-SCS, *Engineering Field Manual for conservation Practices*, or as otherwise determined necessary by the Department.

### SECTION D. ACCESS ROADS (Residual Waste Facilities Must Submit Form 23R)

Access roads shall have drainage system that is compatible with the natural contours, structurally stable, and capable of passing safely the peak flow from a 25-year, 24-hour precipitation event.

Provide the following information for each haul road to be used in the operation.

- a) Show the location on the application's topographic maps;
- b) Description and typical cross sections showing the construction of each access road including existing and proposed contours, grades, slopes, culvert locations, outlet protection, and other drainage control;
- c) Measures to control and prevent erosion and sedimentation; include proposed spacing of sediment traps, turnouts, cross drains, culverts, check dams, stabilized ditches, erosion resistant surfacing, etc.;
- d) Plan for reclamation after the operation is completed;
# ATTACHMENT I-1 NARRATIVE

### ATTACHMENT I-1

### SOIL EROSION AND SEDIMENTATION CONTROL PLAN AND STORMWATER MANAGEMENT PLAN

### **1.0 INTRODUCTION**

This narrative presents discussions and supporting calculations for the Stormwater Management (SWM) Plan and Soil Erosion and Sedimentation Control (E&S) Plan for the vertical expansion of the existing landfill and capping outside the expansion area footprint. This E&S Plan has been prepared to comply with the appropriate standards established by the Pennsylvania Department of Environmental Protection (PADEP) Chapter 102 to reduce accelerated erosion from site activities.

Landfill expansion and capping involves the disturbance and stabilization of the existing landfill (i.e., stages 1, 2, and 3A) and the development of surface water management structures to control stormwater runoff and erosion.

The vertical landfill expansion, above the previously placed ash that made up of Stages 1, 2, and 3A, consists of new areas identified as Stages 4, 5, and 6. Stage 6 provides two options for construction. Stages 4, 5, and 6 include an layover liner or final cover system, and these areas generally correspond to the red, aqua, and green areas designated by the CO&A, respectively. Stage 4 construction sequence consists of an layover liner followed by ash placement and construction of a soil final cover system. Stage 5 construction sequence consists of construction and fill placement. Alternate A construction sequence consists of no ash placement and the construction of a geosynthetics final cover system. Alternate B construction sequence consists of a layover liner, ash fill placement and construction of a soil final cover system in Stages 4, 5, and 6, the portions of Stages 1, 2, and 3A outside of the vertical expansion footprint will be closed with a final cover system.

### 1.1 GENERAL SOIL EROSION/SEDIMENTATION CONTROL

Currently, stormwater runoff is directed to the Sedimentation Pond (Designated as 006 by the NPDES Permit), which is located within the Ash Impoundment at its northwest corner. The Sedimentation Pond is an existing structure that was developed during the filling of the Ash Impoundment. This structure will continue to be used for the management of stormwater collected from the landfill.

040-654.0107-Attachment I-I Dec 2010.doc 100-063.00023 Attachment I-I Dec 2010.doc The expansion and capping of the approximate 60 acre landfill will include revisions to the current stormwater collection network of channels. New and revised perimeter channels have been designed to collect stormwater runoff from the landfill. These channels have been designed to discharge to the existing Sedimentation Pond (006); however, in the temporary condition the channels will discharge to the existing Leachate Pond (009) until the channels are extended to the Sedimentation Pond in 2009completion of the Stage 5 final cover system. In addition, the vertical landfill expansion design includes landfill benches designed in the final cover slopes and they discharge to down chute channels that discharge to the perimeter channels.

A design feature included in the design package as an erosion control measure is the use of decant structures. Within each stage of the expansion, decant structures will be used to collect and transmit stormwater runoff collected from the top of active disposal areas, and the runoff will be conveyed through piping and a lined channel to the leachate pond. This decant structure design has been approved by the PADEP and used at other company disposal sites. The drawings present the alignment and detail for the decant structures.

### 1.2 GENERAL STORMWATER MANAGEMENT

The site will be developed in stages and stormwater controls will be constructed as needed for construction and operation of each landfill stage. Conveyance of stormwater to the Sedimentation Pond will be accomplished through overland flow to landfill benches and a network of stormwater management channels. Lined stormwater channels will be used to direct stormwater to the site's Sedimentation Pond.

### 1.3 <u>REFERENCE DOCUMENTS</u>

The plan presented herein incorporates SWM and E&S features required for the development and final site design in accordance with state standards. References used include:

- 1. HydroCAD 8.09.09.10, HydroCAD Software Solutions LLC.
- 4.2.National Climatic Data Center. Precipitation Frequency Estimates, Point Precipitation Frequency Estimate From NOAA Atlas 14 for New Castle, Pennsylvania, Viewed 28 July 2010, <u>http://hdsc.nws.noaa.gov/hdsc/pfds/index.html</u>.
- 2-3.Soil Conservation Service, <u>URBAN HYDROLOGY FOR SMALL WATERSHEDS</u>, Technical Release 55, June 1986.
- 3.4. "Erosion and Sediment Pollution Control Manual (Chapter 102)," Commonwealth of Pennsylvania Department of Environmental Protection, April 2000.

- 4-5. "Soil Survey for Beaver and Lawrence Counties," United States Department of Agriculture, Soil Conservation Service, April 1982.
- 5-6. Ven Te Chow, <u>OPEN CHANNEL HYDRAULICS</u>, McGraw Hill Book Company, 1959

Refer to Attachment I-2 for SWM and E&S calculations for the proposed expansion area. Refer to the permit drawing set for the proposed features necessary to show a complete SWM and E&S Plan.

### 2.0 PROPOSED FEATURES

The development of the expansion and cap areas will utilize lined stormwater collection channels and the existing Sedimentation Pond for both SWM and E&S control during site development.

### 2.1 DESIGN METHODOLOGY AND ASSUMPTIONS

The following general design assumptions were made in the preparation of the SWM and E&S plans presented herein. Refer to Exhibit I-1 for stormwater routing and designs.

### 2.1.1 General Hydrology

- 1. Peak discharge estimates were developed using the computer program HydroCAD 8.0 9.09.10, HydroCAD Software Solutions LLC.
- 2. Soil types reference the USDA Soil Survey for Somerset Beaver and Lawrence Countyies. Pennsylvania were based on samples taken for final cover and tested in the lab. and, iln general, the samples were a silty loam or loam material which belongs to hydrologic soil group BCB.
- 3. The curve number (CN) of 48 was selected to represent an undisturbed brush/grass mix condition.
- 4. The CN of <del>70</del>-61 was selected to represent a <del>disturbed</del>-final condition with good grass cover.

### 2.2 <u>CHANNELS</u>

Lined channels have been designed to convey stormwater in contact with disturbed areas to the Sedimentation Pond. Refer to the permit drawings for channel locations and details. Stormwater

040-654.0107-Attachment I-1 Dec 2010.doc 100-063.00023 Attachment I-1 Dec 2010.doc volumes are based on the 25--year, 24--hour storm event. Refer to Attachment I-2 for supporting calculations.

### 3.0 SEQUENCE OF OPERATION

Refer to Table I-1.1 for details regarding the staging/sequence of disturbance of the landfill and the earthmoving activities with regard to implementing E&S features.

### 4.0 MAINTENANCE PROGRAM

Refer to Table I-1.2 for a maintenance schedule regarding SWM and E&S features.

040-654.0107-Attachment I-1 Dec 2010.doc 100-063.00023 Attachment I-1 Dec 2010.doc

April 27, 2007 Revised February 2008 Revised November 3, 2008 Revised December 2010

# TABLE I-1.1E&S AND SWM CONSTRUCTION SEQUENCE

### TABLE I-1.1

### **E&S AND SWM CONSTRUCTION SEQUENCE**

The following is a sequential order for the construction of the erosion and sedimentation (E&S) control features associated with the capping and expansion of the landfill. Refer to the permit drawings for plan views of the temporary and permanent E&S control locations.

Note: Landfill overlay layover liner and cap construction will be performed in stages that will occur over a 5.5 year period with significant capping and approximately one third of overlay layover liner construction occurring in the first year.

### CONTROLS FOR DISTURBANCE OF THE LANDFILL

- 1. Install and maintain silt fence or straw bales along contour around the perimeter and down-gradient of areas that are to be disturbed, prior to beginning any earthmoving activities in those areas.
- 2. Stormwater collection channels along the landfill's perimeter are incorporated into the cap construction. Therefore, they will be constructed during cap construction.

### **CONSTRUCTION SEQUENCE**

To maintain access to the site's active disposal area during construction, the cap around the base of the landfill will be constructed in three-two phases, which will be completed by December 31, 2009. Overlay liner Layover liner will be constructed in three phases that will occur over a 5.5 year period following issuance of the permit.

Stage 4 and Closure Area 1 (located south and west of Stage 4) will be constructed first and they will be constructed concurrently (see drawings for the limits of Stage 4 and Closure Area 1). Then Closure Area 2, located along the north and eastern remaining portion of the landfill, will be constructed. followed by Closure Area 3, located along the east and southern portion of the landfill (see drawings for the limits of Closure Areas 2 and 3). Stages 5 and 6 will be constructed individually in separate years following Stage 4 and Closure construction.

### **STAGE 4 AND CLOSURE AREA 1 CONSTRUCTION**

- 1. Install and maintain silt fence or straw bales along the contour at the toe of slope outside of the disturbed area and downgradient of Channel A, Reach 1.
- 2. Install a portion of Channel A, Reach 1 between the existing Leachate Pond and the northwest corner of the landfill. Channel A will temporarily discharge to the Leachate Pond and upon the completion of its construction, it will be routed to discharge into the

### TABLE I-1.1 (Continued)

existing Sedimentation Pond (006). Channel D will run parallel to Channel A and discharge into the Leachate Pond.

- 3. Install Channel A, Reach 2 concurrently with Closure Area 1 construction.
- 4. Install Down Chute 2, Reach 1; Down Chutes 4 and 5; and the Decant Down Chute concurrently with the completion of Closure Area 1.
- 5. Following the construction of the Stage 4 layover liner and during waste filling, in areas where final grade has been achieved up to each landfill bench, construct a temporary liner in Down Chute 2, Reach 2. The temporary liner used shall provide the same protection from erosion as the final liner configuration.

### **CLOSURE AREA 2 CONSTRUCTION**

- 1. Install and maintain silt fence or straw bales along the contour at the toe of slope outside of the disturbed area and down-gradient of Channel B, Reach 1.
- 2. Install Down Chute 1, Reach 1; Channel A, Reach 1 to the sedimentation pond; Channel B, Reach 1 between Channel A, Reach 1 and the north west corner of the landfill.
- 3. Install Channel B, Reach 2 concurrently with Closure Area 2 construction.
- 4. Install Down Chute 3, Reach 1 concurrently with Closure Area 2 construction.
- 5. Install Channel A, Reach 3 and the remaining portion of Channel B, Reach 2 concurrently with Closure Area 3 construction.

### **CLOSURE AREA 3 CONSTRUCTION**

1. Install and maintain silt fence or straw bales along the contour at the toe of slope outside of the disturbed area.

### **STAGE 5 CONSTRUCTION**

1. Install and maintain silt fence or straw bales as needed to protect down gradient final cover.

040-654.0107-Attachment I-1 100-063.0003 Attachment I-1 Dec 2010.doc

### TABLE I-1.1 (Continued)

2.—Following the construction of the Stage 5 layover liner and during waste filling, in areas where final grade has been achieved up to each landfill bench, construct a temporary liner in Down Chute 1. Reach 2, and Down Chute 3, Reach 2.—The temporary liner used shall provide the same protection from erosion as the final liner configuration final cover system, channels and down chutes shall be constructed according to the design.

### **STAGE 6A CONSTRUCTION**

- 1. Install and maintain silt fence or straw bales as needed to protect down gradient final cover.
- 2. Following the construction of the stage 6a final cover system, channels and down chutes shall be constructed according to the design.

### **STAGE 6B CONSTRUCTION**

- 1. Install and maintain silt fence or straw bales as needed to protect down gradient final cover.
- 2. Following the construction of the Stage 6B layover liner and during waste filling, in areas where final grade has been achieved up to each landfill bench, construct a temporary liner in Channel-Cchannels and down chutes. The temporary liner used shall provide the same protection from erosion as the final liner configuration.
- 3. Following Completion of Waste Filling in Stage 6B, the final cover system, channels and down chutes shall be constructed according to the design.

### **STAGE 7 CONSTRUCTION**

1. During waste filling in Stage 7, in areas where final grade has been achieved up to each landfill bench, construct a temporary liner in Channel C and Down Chutes 1, 2, and 3. The temporary liners used shall provide the same protection from erosion as the final liner configuration.

### CLOSURE OF STAGES 4, 5, 6, AND 7

4. Install and maintain silt fence or straw bales as needed to protect down gradient final cover.

### TABLE I-1.1 (Continued)

2.—Concurrently with the Closure of Stages 4. 5. 6. and 7. Channel C and Down Chutes 1, 2, and 3 shall be constructed according to the design.

# TABLE I-1.2E&S AND SWM INSPECTIONFREQUENCY AND MAINTENANCE PLAN

TABLE I-1.2E&S AND SWM INSPECTION FREQUENCY AND MAINTENANCE PLAN

Feature	Inspection Frequency	Maintenance
Channels, Benches, and/or Ponds	Weekly and after precipitation events that produce at least 0.5 inches of rainfall within a four hour period, until the drainage areas are stabilized. *	Remove sediment/debris as necessary to maintain the total design depth.
Silt Fence	Silt Fence Weekly and after all runoff events until drainage areas are stabilized. * Repair any erosion rills fence. Repair silt fence collapses caused by ins filter outlets at these lo Remove sediment from fence when it accumul 1/2 the height of the fa	
Vegetation	Weekly and after all runoff events until the area is stabilized. *	Regrade, seed, fertilize, and mulch as needed to stabilize disturbed areas (Refer to the revegetation measures in Form H for more information).
Dust	Daily when conditions dictate.	Add moisture, vegetate, or apply mulch to open bare areas during dry periods.
Temporary Control Measures and Facilities	Weekly and after all runoff events until stabilized. *	Remove sediment/debris and repair as needed to conform to installation specifications.
Rock Filters/ Aprons	Weekly and after all runoff events until stabilized. *	Replace clogged filter stone and/or stone as necessary.

\*Stabilization occurs when there is at least a uniform, 70 percent vegetative cover established over the up gradient area.

# EXHIBIT I-1 E&S AND SWM DESIGN CALCULATIONS

# EXHIBIT I-1.1 CALCULATION BRIEF



Civil & Environmental Consultants, Inc.								
PROJECT NEW CASTLE PLANT ASH LANDFILL PROJECT NO. 040654.0109								
STORM WA	PAGE	1	OF	3				
 MADE BY	GDT	DATE	4/27/2007	CHECKED BY		DATE		
	Rev. DMF		Revised 1/28/08					
	Rev. PAW		Revised 11/3/08					
	Rev. JJK		Revised 9/16/10	_	DMT	<b>_</b> .	1/201	10

### **Design Objective:**

Design the storm water management system for the expansion area. This design includes landfill down chute channels, perimeter channels, and channels outside the disposal area to the Sedimentation Pond. In addition to the stormwater channels, a landfill bench lining was designed.

### **Design Method & Conditions:**

The Soil Conservation Service (SCS) technical Release No. 20 (TR-20) methodology within the HydroCAD computer program was used to determine the peak 25-year 24-hour runoff rates. The precipitation amount for the 25-year 24-hour storm event in Lawrence County was based on <u>National Climatic Data Center</u>, <u>Precipitation Frequency Estimates</u>, <u>Point</u> <u>Precipitation Frequency Estimate From NOAA Atlas 14.Table 1</u>, <u>Pennsylvania-Rainfall By</u> <u>Counties</u>, provided in the PA DEP E&S Control Program Manual, dated April 2000. HydroCAD was used to design the channels, down chutes, and culverts. Then, Standard Worksheet #21 for Channel Design Data from the PADEP E&S Control Program Manual was used to complete each channel design. <u>A CN of 61 was selected to represent a final</u> <u>condition with good grass cover</u>. Worksheet #21 was used to design the channel linings and depth with freeboard.

### **Calculations:**

After the final landfill configuration was designed, the limits of the watersheds contributing to stormwater channels were outlined and subdivided into sub-watersheds, including sub-watersheds for the landfill benches. Watershed areas, slope grades, and channel configurations along with runoff curve numbers were input into HydroCAD, which calculated runoff data for each sub-watershed and each channel.

The data generated by HydroCAD, was used in PA's E&S Control Program Manual Worksheet # 21 to design the final configuration and lining of each channel. See Exhibit I-1.2 for the HydroCAD output for Alternates 6A and 6B. The perimeter channels were evaluated with these tools and after sizing the channels it was determined that a grass lining was sufficient



Civil & Environmental Consultants, Inc.								
PROJECT NEV	V CASTLE P	LANT A		PROJECT N	O	04065	4.0109	
STORM WA	PAGE	2	OF	3				
MADE BY	GDT	DATE	4/27/2007	CHECKED BY		DATE		
	Rev. DMF		<b>Revised 1/28/08</b>					
Rev. PAW Revised 11/3/08					,	,		
	Rev. JJK		Revised 9/16/10	_	DUT		11/29	10

for the channels. Refer to Exhibit I-1.3 and I-1.4 for Standard Worksheet #21 Channel Design Data calculations.

Based on the requirements included in Pennsylvania's Manual, channels with slopes of greater than 10 percent were evaluated for a riprap liner. In this design, this included all of the down chute channels. Based on the design requirements for a rip rap liner, a concrete revetment liner was selected for the down chute channel linings. This lining has been used at other facilities associated with Orion, and it has performed well in similar applications. Refer to Exhibit I-1.3 and I-1.4 for Standard Worksheet #21 Channel Design Data calculations.

At the discharge point of each down chute channel into the perimeter channels, a concrete revetment liner will be installed in the perimeter channels. To prevent down chute discharges from passing straight through the perimeter channel and overtopping its outerbank, 3-ft x 3-ft gabion basket will be constructed along the perimeter channel's outer-bank. Construction of the gabion baskets is graphically shown in the stormwater details on the drawings. Both the concrete revetment liner and the gabion baskets will extend up-gradient and down-gradient 5-ft from the channel.

A grass lining evaluation was performed on the landfill benches. Worksheet #21 was used to determine if a grass lining has sufficient resistance to the maximum velocity and maximum flow volume. For this evaluation, the HydroCAD output data was scanned for the worst case data which was entered into Worksheet #21 (see Exhibit I-1.5). The grass lining was found to have sufficient shear resistance and is an acceptable lining material.

### **Conclusions:**

Based on the calculations attached, the channel configurations proposed for the landfill provide sufficient capacity and lining velocity or shear resistance for the design flows.

### **References:**

1. Soil Conservation Service, <u>URBAN HYDROLOGY FOR SMALL</u> <u>WATERSHEDS</u>, Technical Release 55, June 1986.



Civil & Environmental Consultants, Inc.									
PROJECT NEW CASTLE PLANT ASH LANDFILL PROJECT NO. 040654.0109									
STORM WA	STORM WATER MANAGEMENT DESIGN							OF	3
MADE BY	MADE BY <b>GDT</b> DATE		4/27/2007	CHECKED BY			DATE		
	Rev. DMF		<b>Revised 1/28/08</b>						
	Rev. PAW		Revised 11/3/08		Ace	T			1
	Nev. JJK		Keviseu 9/10/10	-	<u>DM</u>			11/29/	10

- 2. PADEP, <u>EROSION AND SEDIMENTATION POLLUTION CONTROL</u> <u>PROGRAM MANUAL</u>, April 2000.
- 3. Ven Te Chow, <u>OPEN CHANNEL HYDRAULICS</u>, Mc-Graw Hill Book Company, 1959
- 4. HydroCAD 8.0, HydroCAD Software Solutions LLC.

# EXHIBIT I-1.2.1 ALTERNATE 6A - HYDROCAD OUTPUT



### Area Listing (all nodes)

Area	CN	Description
(acres)		(subcatchment-numbers)
132.848	61	(2S, 20S, 28S, 30S, 53S, 55S, 57S, 59S, DA-10, DA-11, DA-12, DA-13, DA-14,
		DA-15, DA-16, DA-17, DA-18, DA-19, DA-2, DA-20, DA-21, DA-3, DA-4, DA-5,
		DA-6, DA-7A, DA-7B, DA-8, DA-9)
0.500	61	>75% Grass Cover, Good HGB (DA-1)
133.348	61	TOTAL AREA

### Soil Listing (all nodes)

Area	Soil	Subcatchment
(acres)	Group	Numbers
0.000	HSG A	
0.000	HSG B	
0.000	HSG C	
0.000	HSG D	
133.348	Other	2S, 20S, 28S, 30S, 53S, 55S, 57S, 59S, DA-1, DA-10, DA-11, DA-12, DA-13,
		DA-14, DA-15, DA-16, DA-17, DA-18, DA-19, DA-2, DA-20, DA-21, DA-3, DA-4,
		DA-5, DA-6, DA-7A, DA-7B, DA-8, DA-9
133.348	5	TOTAL AREA

### Phase 6A10-18-10

### Pipe Listing (all nodes)

Line#	Node	In-Invert	Out-Invert	Length	Slope	n	Diam/Width	Height	Fill
	Number	(feet)	(feet)	(feet)	(ft/ft)		(inches)	(inches)	(inches)
1	11P	762.00	761.50	50.0	0.0100	0.015	24.0	0.0	0.0
2	34P	784.35	784.10	50.0	0.0050	0.010	24.0	0.0	0.0
3	55P	776.00	775.00	40.0	0.0250	0.025	36.0	0.0	0.0
4	62P	770.51	770.42	24.0	0.0038	0.011	30.0	0.0	0.0

Phase 6A10-18-10

Prepared by Microsoft HydroCAD® 9.10 s/n 01006 © 2010 HydroCAD Software Solutions LLC

> Time span=0.00-24.00 hrs, dt=0.01 hrs, 2401 points Runoff by SCS TR-20 method, UH=SCS Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment 2S: SB4	Runoff Area=2.300 ac 0.00% Impervious Runoff Depth>0.71"
Flov	v Length=2,550' Tc=197.9 min CN=61 Runoff=0.31 cfs 0.135 af
Subcatchment 20S: SB6	Runoff Area=5.780 ac 0.00% Impervious Runoff Depth>0.78"
Flow Length=270	' Slope=0.1000 '/' Tc=6.4 min CN=61 Runoff=7.19 cfs 0.373 af
Subcatchment 28S: SB 1	Runoff Area=2.310 ac 0.00% Impervious Runoff Depth>0.77"
Flow Length=300'	Slope=0.0250 '/' Tc=12.0 min CN=61 Runoff=2.21 cfs 0.149 af
Subcatchment 30S: 2	Runoff Area=8.110 ac 0.00% Impervious Runoff Depth>0.77"
Flow Length=480'	Slope=0.0158 '/' Tc=16.9 min CN=61 Runoff=6.35 cfs 0.521 af
Subcatchment 53S: SB 3	Runoff Area=7.870 ac 0.00% Impervious Runoff Depth>0.78" Flow Length=121' Tc=2.3 min CN=61 Runoff=11.79 cfs 0.509 af
Subcatchment 55S: SB12	Runoff Area=46.500 ac 0.00% Impervious Runoff Depth>0.77"
Flow Length=1,050'	Slope=0.0600 '/' Tc=13.6 min CN=61 Runoff=41.55 cfs 2.994 af
Subcatchment 57S: SB 11	Runoff Area=4.040 ac 0.00% Impervious Runoff Depth>0.77"
Flow Length=300'	Slope=0.0313 '/' Tc=11.0 min CN=61 Runoff=4.05 cfs 0.260 af
Subcatchment 59S: SB 13	Runoff Area=0.578 ac 0.00% Impervious Runoff Depth>0.78"
Flow Length=55	' Slope=0.0720 '/' Tc=2.0 min CN=61 Runoff=0.88 cfs 0.037 af
Subcatchment DA-1: Area 1	Runoff Area=0.500 ac 0.00% Impervious Runoff Depth>0.77"
Flow Length=114	' Slope=0.1930 '/' Tc=7.4 min CN=61 Runoff=0.59 cfs 0.032 af
Subcatchment DA-10: Area 10	Runoff Area=9.240 ac 0.00% Impervious Runoff Depth>0.77"
Flow Length=444'	Slope=0.0428 '/' Tc=31.2 min CN=61 Runoff=4.75 cfs 0.590 af
Subcatchment DA-11: Area 11	Runoff Area=2.770 ac 0.00% Impervious Runoff Depth>0.78"
Flow Length=30	' Slope=0.3330 '/' Tc=2.1 min CN=61 Runoff=4.18 cfs 0.179 af
Subcatchment DA-12: Area 12	Runoff Area=1.660 ac 0.00% Impervious Runoff Depth>0.78"
Flow Length=83	' Slope=0.2891 '/' Tc=4.9 min CN=61 Runoff=2.22 cfs 0.107 af
Subcatchment DA-13: Area 13	Runoff Area=1.300 ac 0.00% Impervious Runoff Depth>0.78"
Flow Length=61	' Slope=0.1951 '/' Tc=4.5 min CN=61 Runoff=1.77 cfs 0.084 af
Subcatchment DA-14: Area 14	Runoff Area=1.270 ac 0.00% Impervious Runoff Depth>0.77"
Flow Length=108	Slope=0.1682 '/' Tc=7.5 min CN=61 Runoff=1.50 cfs 0.082 af
Subcatchment DA-15: Area 15	Runoff Area=0.550 ac 0.00% Impervious Runoff Depth>0.77"
Flow Length=114	Slope=0.1491 '/' Tc=8.2 min CN=61 Runoff=0.63 cfs 0.035 af
Subcatchment DA-16: Area 16	Runoff Area=2.020 ac 0.00% Impervious Runoff Depth>0.77"
Flow Length≈197'	Slope=0.1036 '/' Tc=14.8 min CN=61 Runoff=1.72 cfs 0.130 af

Phase 6A10-18-10	Type II 24-hr 25yr/24hr NOAA Rainfall=3.93"
Prepared by Microsoft	Printed 11/19/2010
HydroCAD® 9.10 s/n 01006 © 2010 HydroC	CAD Software Solutions LLC Page 6
Subcatchment DA-17: Area 17	Runoff Area=0.440 ac 0.00% Impervious Runoff Depth>0.77"
Flow Length=138	8' Slope=0.1231 '/' Tc=10.4 min CN=61 Runoff=0.45 cfs 0.028 af
Subcatchment DA-18: Area 18	Runoff Area=1.400 ac 0.00% Impervious Runoff Depth>0.77"
Flow Length=464	4' Slope=0.0320 '/' Tc=35.3 min CN=61 Runoff=0.66 cfs 0.089 af
Subcatchment DA-19: Area 19	Runoff Area=2.240 ac 0.00% Impervious Runoff Depth>0.77"
Flow Length=11	13' Slope=0.1240 '/' Tc=8.8 min CN=61 Runoff=2.49 cfs 0.145 af
Subcatchment DA-2: Area 2	Runoff Area=3.100 ac 0.00% Impervious Runoff Depth>0.77"
Flow Length=12	20' Slope=0.2500 '/' Tc=7.0 min CN=61 Runoff=3.75 cfs 0.200 af
Subcatchment DA-20: Area 20	Runoff Area=2.350 ac 0.00% Impervious Runoff Depth>0.77"
Flow Length=378	8' Slope=0.0343 '/' Tc=33.2 min CN=61 Runoff=1.15 cfs 0.150 af
Subcatchment DA-21: Area 21	Runoff Area=0.600 ac 0.00% Impervious Runoff Depth>0.78" Flow Length=265' Tc=3.9 min CN=61 Runoff=0.84 cfs 0.039 af
Subcatchment DA-3: Area 3	Runoff Area=6.920 ac 0.00% Impervious Runoff Depth>0.77"
Flow Length=204	4' Slope=0.0980 '/' Tc=15.5 min CN=61 Runoff=5.72 cfs 0.445 af
Subcatchment DA-4: Area 4	Runoff Area=1.260 ac 0.00% Impervious Runoff Depth>0.77"
Flow Length=197	7' Slope=0.1230 '/' Tc=13.8 min CN=61 Runoff=1.12 cfs 0.081 af
Subcatchment DA-5: Area 5	Runoff Area=8.780 ac 0.00% Impervious Runoff Depth>0.77" Flow Length=374' Tc=36.3 min CN=61 Runoff=4.04 cfs 0.560 af
Subcatchment DA-6: Area 6	Runoff Area=3.370 ac 0.00% Impervious Runoff Depth>0.78" Flow Length=752' Tc=6.1 min CN=61 Runoff=4.26 cfs 0.218 af
Subcatchment DA-7A: Area 7	Runoff Area=1.440 ac 0.00% Impervious Runoff Depth>0.76"
Flow Length=510	0' Slope=0.0196 '/' Tc=43.9 min CN=61 Runoff=0.57 cfs 0.091 af
Subcatchment DA-7B: Area 7B	Runoff Area=2.640 ac 0.00% Impervious Runoff Depth>0.76"
Flow Length=45	1' Slope=0.0232 '/' Tc=40.0 min CN=61 Runoff=1.13 cfs 0.168 af
Subcatchment DA-8: Area 8	Runoff Area=0.220 ac 0.00% Impervious Runoff Depth>0.78"
Flow Length=0	64' Slope=0.2982 '/' Tc=3.9 min CN=61 Runoff=0.31 cfs 0.014 af
Subcatchment DA-9: Area 9	Runoff Area=1.790 ac 0.00% Impervious Runoff Depth>0.77" Flow Length=579' Tc=11.6 min CN=61 Runoff=1.75 cfs 0.115 af
Reach 1R: Downchute 10 n=0.015 L=	Avg. Flow Depth=0.09' Max Vel=6.95 fps Inflow=1.74 cfs 0.238 af 116.0' S=0.1293 '/' Capacity=273.14 cfs Outflow=1.74 cfs 0.238 af
Reach 2R: South Berm Channel 10 n=0.030 L:	Avg. Flow Depth=0.40' Max Vel=1.62 fps Inflow=0.66 cfs 0.089 af =158.0' S=0.0100 '/' Capacity=47.07 cfs Outflow=0.65 cfs 0.089 af
Reach 3R: Channel A, Reach 6	Avg. Flow Depth=0.33' Max Vel=2.72 fps Inflow=4.40 cfs 0.676 af
n=0.030 L:	=60.0' S=0.0175 '/' Capacity=148.09 cfs Outflow=4.40 cfs 0.675 af

Phase 6A10-18-10

HydroCAD® 9.10 s/n 01006 © 2010 HydroCAD Software Solutions LLC	Page 7
Reach 4R: Downchute 6 Reach 1Avg. Flow Depth=0.13'Max Vel=8.53 fpsInflow=3.00 cfsn=0.015L=125.0'S=0.1328 '/'Capacity=276.80 cfsOutflow=3.00 cfs	0.512 af 0.512 af
Reach 5R: South Berm Channel, Reach Avg. Flow Depth=0.11' Max Vel=1.12 fps Inflow=2.49 cfs n=0.030 L=1,036.0' S=0.0097 '/' Capacity=50.55 cfs Outflow=1.24 cfs	0.145 af 0.141 af
Reach 6R: Downchute 7 Avg. Flow Depth=0.15' Max Vel=10.80 fps Inflow=4.59 cfs   n=0.015 L=237.0' S=0.1741 '/' Capacity=138.94 cfs Outflow=4.58 cfs	0.255 af 0.255 af
Reach 7R: Channel A, Reach 2 Avg. Flow Depth=0.73' Max Vel=2.17 fps Inflow=11.83 cfs   n=0.030 L=510.0' S=0.0039 '/' Capacity=75.34 cfs Outflow=11.73 cfs	2.051 af 2.041 af
Reach 8R: South Berm Channel, Reach Avg. Flow Depth=0.15' Max Vel=1.77 fps Inflow=2.57 cfs n=0.030 L=174.0' S=0.0172 '/' Capacity=67.57 cfs Outflow=2.57 cfs	0.407 af 0.406 af
Reach 9R: East Berm Channel 10 Stage Avg. Flow Depth=0.49' Max Vel=1.81 fps Inflow=1.15 cfs n=0.030 L=620.2' S=0.0097 '/' Capacity=46.29 cfs Outflow=1.09 cfs	0.150 af 0.149 af
Reach 10R: North Berm Channel 1 Avg. Flow Depth=0.31' Max Vel≈2.03 fps Inflow=4.04 cfs   n=0.030 L=1,050.0' S=0.0100 '/' Capacity=31.43 cfs Outflow=3.70 cfs	0.560 af 0.553 af
Reach 11R: Down Chute 11 Avg. Flow Depth=0.08' Max Vel=5.63 fps Inflow=1.12 cfs   n=0.015 L=108.0' S=0.1111 '/' Capacity=253.19 cfs Outflow=1.12 cfs	0.168 af 0.168 af
Reach 16R: Junction Avg. Flow Depth=0.50' Max Vel=17.37 fps Inflow=42.94 cfs   n=0.010 L=96.4' S=0.0467 '/' Capacity=591.65 cfs Outflow=42.94 cfs	4.278 af 4.278 af
Reach 21R: Clean water diversion ditch Avg. Flow Depth=1.59' Max Vel=5.09 fps Inflow=45.53 cfs n=0.010 L=1,113.5' S=0.0013 '/' Capacity=175.83 cfs Outflow=41.84 cfs	3.368 af 3.352 af
Reach 22R: Clean water diversion ditch Avg. Flow Depth=1.22' Max Vel=7.69 fps Inflow=41.97 cfs n=0.010 L=490.4' S=0.0041 '/' Capacity=306.69 cfs Outflow=41.68 cfs	3.389 af 3.384 af
Reach 25R: Channel A Reach 1 Avg. Flow Depth=0.97' Max Vel=2.40 fps Inflow=20.76 cfs   n=0.030 L=132.0' S=0.0037 '/' Capacity=85.69 cfs Outflow=20.74 cfs	4.010 af 4.006 af
Reach 29R: Clean water diversion ditch Avg. Flow Depth=1.50' Max Vel=5.67 fps Inflow=43.47 cfs n=0.010 L=668.4' S=0.0018 '/' Capacity=202.13 cfs Outflow=42.44 cfs	3.533 af 3.524 af
Reach 31R: Clean water diversion ditch Avg. Flow Depth=1.74' Max Vel=4.33 fps Inflow=48.63 cfs n=0.010 L=1,485.0' S=0.0009 '/' Capacity=141.74 cfs Outflow=41.43 cfs	4.046 af 4.018 af
Reach 33R: Channel A, Reach 7 Avg. Flow Depth=0.27' Max Vel=1.00 fps Inflow=1.72 cfs   n=0.030 L=535.0' S=0.0030 '/' Capacity=61.22 cfs Outflow=1.28 cfs	0.130 af 0.128 af
Reach 39R: Channel A, Reach 5 Avg. Flow Depth=0.82' Max Vel=1.24 fps Inflow=7.39 cfs   n=0.030 L=613.0' S=0.0012 '/' Capacity=31.93 cfs Outflow=5.73 cfs	0.935 af 0.925 af
Reach 45R: Channel A, Reach 4 Avg. Flow Depth=0.67' Max Vel=2.86 fps Inflow=10.44 cfs   n=0.030 L=900.0' S=0.0082 '/' Capacity=82.49 cfs Outflow=10.17 cfs	1.599 af 1.588 af

Phase 6A10-18-10 Type II 24-hr 25yr/24hr NOAA Rainfall=3.93" Printed 11/19/2010 Prepared by Microsoft HydroCAD® 9.10 s/n 01006 © 2010 HydroCAD Software Solutions LLC Page 8 Reach 46R: Channel A, Reach 3 Avg. Flow Depth=0.76' Max Vel=2.55 fps Inflow=10.65 cfs 1.717 af n=0.030 L=176.0' S=0.0057 '/' Capacity=68.81 cfs Outflow=10.64 cfs 1.715 af Reach 51R: Channel B, Reach 2 Avg. Flow Depth=0.47' Max Vel=1.81 fps Inflow=4.79 cfs 0.892 af n=0.030 L=1,063.0' S=0.0052 '/' Capacity=80.53 cfs Outflow=4.55 cfs 0.881 af Avg. Flow Depth=0.80' Max Vel=2.21 fps Inflow=12.65 cfs 1.975 af Reach 55R: Channel B, Reach 1 n=0.030 L=352.0' S=0.0043 '/' Capacity=73.08 cfs Outflow=11.28 cfs 1.969 af Avg. Flow Depth=0.38' Max Vel=1.54 fps Inflow=5.72 cfs 0.445 af Reach 56R: Channel B, Reach 3 n=0.030 L=1,730.0' S=0.0046 '/' Capacity=76.13 cfs Outflow=3.04 cfs 0.434 af Avg. Flow Depth=0.05' Max Vel=6.28 fps Inflow=0.84 cfs 0.039 af Reach 57R: Downchute 8 n=0.015 L=160.0' S=0.2250 '/' Capacity=157.93 cfs Outflow=0.84 cfs 0.039 af Avg. Flow Depth=0.20' Max Vel=10.27 fps Inflow=2.83 cfs 0.177 af Reach 58R: Downchute 5 n=0.015 L=107.0' S=0.1393 '/' Capacity=74.29 cfs Outflow=2.83 cfs 0.177 af Avg. Flow Depth=0.09' Max Vel=6.61 fps Inflow=1.58 cfs 0.106 af Reach 59R: Downchute 6 Reach 3 n=0.015 L=97.0' S=0.1237 '/' Capacity=267.16 cfs Outflow=1.58 cfs 0.106 af Reach 60R: Downchute 6 Reach 2 Avg. Flow Depth=0.15' Max Vel=7.38 fps Inflow=3.00 cfs 0.512 af n=0.015 L=23.5' S=0.0851 '/' Capacity=221.59 cfs Outflow=3.00 cfs 0.512 af Avg. Flow Depth=0.49' Max Vel=1.88 fps Inflow=1.13 cfs 0.168 af Reach 61R: East Berm Channel 11 n=0.030 L=248.0' S=0.0105 '/' Capacity=48.19 cfs Outflow=1.12 cfs 0.168 af Avg. Flow Depth=0.07' Max Vel=8.88 fps Inflow=1.75 cfs 0.115 af Reach 62R: Downchute 4 n=0.015 L=82.0' S=0.2805 '/' Capacity=176.33 cfs Outflow=1.75 cfs 0.115 af Reach 63R: Channel A Outlet Avg. Flow Depth=1.04' Max Vel=2.12 fps Inflow=20.74 cfs 4.006 af n=0.030 L=905.2' S=0.0027 '/' Capacity=72.72 cfs Outflow=20.15 cfs 3.973 af Avg. Flow Depth=0.27' Max Vel=4.10 fps Inflow=4.18 cfs 0.179 af Reach 64R: Channel C n=0.030 L=1,591.0' S=0.0534 '/' Capacity=33.23 cfs Outflow=2.83 cfs 0.177 af Avg. Flow Depth=0.17' Max Vel=2.02 fps Inflow=2.22 cfs 0.107 af Reach 65R: Channel E n=0.030 L=796.0' S=0.0201 '/' Capacity=37.94 cfs Outflow=1.58 cfs 0.106 af Reach 66R: Northeast Berm Channel 3 Avg. Flow Depth=0.11' Max Vel=1.50 fps Inflow=1.69 cfs 0.259 af n=0.030 L=347.0' S=0.0173 '/' Capacity=239.62 cfs Outflow=1.68 cfs 0.258 af Avg. Flow Depth=0.04' Max Vel=5.55 fps Inflow=0.57 cfs 0.091 af Reach 67R: Downchute 9 n=0.015 L=43.0' S=0.2326 '/' Capacity=366.30 cfs Outflow=0.57 cfs 0.091 af Avg. Flow Depth=0.26' Max Vel=3.15 fps Inflow=4.26 cfs 0.218 af Reach 68R: Channel F Reach 1 n=0.030 L=465.0' S=0.0301 '/' Capacity=46.43 cfs Outflow=3.96 cfs 0.217 af Avg. Flow Depth=0.15' Max Vel=9.76 fps Inflow=3.96 cfs 0.217 af Reach 69R: Channel F Reach 2 n=0.015 L=134.0' S=0.1493 '/' Capacity=128.63 cfs Outflow=3.96 cfs 0.217 af

Phase 6A10-18-10	Type II 24-hr 25yr/24hr NOAA Rai	nfall=3.93"
Prepared by Microsoft	Printed	11/19/2010
HydroCAD® 9.10 s/n 01006 © 2010 H	lydroCAD Software Solutions LLC	Page 9
Reach 91R: Downchute 1	Avg. Flow Depth=0.13' Max Vel=10.22 fps Inflow=3.70	ofs 0.553 af
n=0.01	5 L=130.0' S=0.1846 '/' Capacity=326.36 cfs Outflow=3.70 (	ofs 0.553 af
Reach 142R: Downchute 3, Reach	1 Avg. Flow Depth=0.08' Max Vel=8.22 fps Inflow=1.68	cfs_0.258 af
n=0.01	5 L=126.0' S=0.2302 '/' Capacity=364.40 cfs Outflow=1.68	cfs 0.257 af
Reach 171R: Downchute 2	Avg. Flow Depth=0.15' Max Vel=11.23 fps Inflow=4.75	cfs 0.590 af
n=0.01	5 L=479.0' S=0.1892 '/' Capacity=330.43 cfs Outflow=4.74	cfs 0.590 af
Pond 11P: Designed Sed Pond	Peak Elev=763.35' Storage=3.932 af Inflow=57.25	cfs_8 386 af
Primary=7	.36 cfs 5.438 af Secondary=0.00 cfs 0.000 af Outflow=7.36	cfs 5.438 af
Pond 34P: Culvert 1	Peak Elev=785.38' Inflow=4.40	cfs 0.675 af
24.0	" Round Culvert n=0.010 L=50.0' S=0.0050 '/' Outflow=4.40	cfs 0.675 af
Pond 55P: Culvert #3	Peak Flev=777 39' Inflow=10 17	cfs_1.588.af
36.0"	Round Culvert n=0.025 L=40.0' S=0.0250 '/' Outflow=10.17	cfs 1.588 af
Pond 62P: Culvert No.4	Peak Elev=772.19' Inflow=20.74	cfs 4.006 af
30.0" Round	Culvert x 2.00 n=0.011 L=24.0' S=0.0038 '/' Outflow=20.74	cfs 4.006 af

на. По стали и стал По стали и стали

.

Total Runoff Area = 133.348 acRunoff Volume = 8.565 afAverage Runoff Depth = 0.77"100.00% Pervious = 133.348 ac0.00% Impervious = 0.000 ac

### Summary for Subcatchment 2S: SB4

Runoff = 0.31 cfs @ 14.74 hrs, Volume= 0.135 af, Depth> 0.71"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Type II 24-hr 25yr/24hr NOAA Rainfall=3.93"

	Area	(ac) C	N Des	cription		
*	2.	300 6	61			
	2.	300	100.	00% Pervi	ous Area	
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
	61.0	300	0.0193	0.08		Sheet Flow, Sheet Flow Portion for SB4 Woods: Light underbrush n= 0.400 P2= 2.37"
	136.9	2,250	0.0030	0.27		Shallow Concentrated Flow, Shallow Concentrated Flow Woodland Kv= 5.0 fps
	107.0	0.550				

197.9 2,550 Total

### Subcatchment 2S: SB4



### Summary for Subcatchment 20S: SB6

Runoff = 7.19 cfs @ 11.99 hrs, Volume= 0.373 af, Depth> 0.78"



### Summary for Subcatchment 28S: SB 1

Runoff = 2.21 cfs @ 12.06 hrs, Volume= 0.149 af, Depth> 0.77"



### Summary for Subcatchment 30S: 2

Runoff = 6.35 cfs @ 12.12 hrs, Volume= 0.521 af, Depth> 0.77"

Α	rea (	(ac) (	CN De	scription			
*	8.	110	61				
8.110		100	).00% Pervi	ous Area			
(m	Tc nin)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
1	4.5	300	0.0158	0.35		Sheet Flow,	
	2.4	180	0.0158	1.26		Cultivated: Residue<=20% n= 0.060 P2= 2.37" Shallow Concentrated Flow, Nearly Bare & Untilled Kv= 10.0 fps	
1	6.9	480	Total				
Subcatchment 30S: 2							



### Summary for Subcatchment 53S: SB 3

Runoff = 11.79 cfs @ 11.94 hrs, Volume= 0.509 af, Depth> 0.78"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Type II 24-hr 25yr/24hr NOAA Rainfall=3.93"

	Area	(ac) C	N Des	cription		
*	7.	870	61			
7.870			100.	00% Pervi	ous Area	
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
	0.2	1	0.0080	0.08		Sheet Flow,
	2.1	120	0.3330	0.97		Cultivated: Residue<=20% n= 0.060 P2= 2.37" Sheet Flow, Cultivated: Residue<=20% n= 0.060 P2= 2.37"
	23	121	 Total			Cultivated. Residue <- 20 % 11- 0.000 F2- 2.37

Subcatchment 53S: SB 3



### Summary for Subcatchment 55S: SB12

Runoff = 41.55 cfs @ 12.08 hrs, Volume= 2.994 af, Depth> 0.77"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Type II 24-hr 25yr/24hr NOAA Rainfall=3.93"

	Area	(ac) C	N Dese	cription		
*	46.	500 6	51			
46.500		500	100.00% Pervious Area			
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
	8.5	300	0.0600	0.59		Sheet Flow, Cultivated: Residue<=20% n= 0.060 P2= 2.37"
	5.1	750	0.0600	2.45		Shallow Concentrated Flow, Nearly Bare & Untilled Kv= 10.0 fps
_	12.6	1 050	Total			

13.6 1,050 Total

### Subcatchment 55S: SB12



### Summary for Subcatchment 57S: SB 11

Runoff = 4.05 cfs @ 12.05 hrs, Volume= 0.260 af, Depth> 0.77"



### Summary for Subcatchment 59S: SB 13

Runoff = 0.88 cfs @ 11.93 hrs, Volume= 0.037 af, Depth> 0.78"



### Summary for Subcatchment DA-1: Area 1

Runoff = 0.59 cfs @ 12.01 hrs, Volume= 0.032 af, Depth> 0.77"


# Summary for Subcatchment DA-10: Area 10

Runoff = 4.75 cfs @ 12.31 hrs, Volume= 0.590 af, Depth> 0.77"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Type II 24-hr 25yr/24hr NOAA Rainfall=3.93"

	Area	(ac) C	N Des	cription			
*	9.	240 (	61				
	9.	240	100.	00% Pervi	ous Area		
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
	29.5	300	0.0428	0.17		Sheet Flow, n= 0.240 P2= 2.37"	
	1.7	144	0.0428	1.45		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps	
	31.2	444	Total				

### Subcatchment DA-10: Area 10



### Summary for Subcatchment DA-11: Area 11

Runoff = 4.18 cfs @ 11.94 hrs, Volume= 0.179 af, Depth> 0.78"



### Summary for Subcatchment DA-12: Area 12

Runoff = 2.22 cfs @ 11.97 hrs, Volume= 0.107 af, Depth> 0.78"



### Summary for Subcatchment DA-13: Area 13

Runoff = 1.77 cfs @ 11.97 hrs, Volume= 0.084 af, Depth> 0.78"



### Summary for Subcatchment DA-14: Area 14

Runoff = 1.50 cfs @ 12.01 hrs, Volume= 0.082 af, Depth> 0.77"



### Summary for Subcatchment DA-15: Area 15

Runoff = 0.63 cfs @ 12.01 hrs, Volume= 0.035 af, Depth> 0.77"



### Summary for Subcatchment DA-16: Area 16

Runoff = 1.72 cfs @ 12.09 hrs, Volume= 0.130 af, Depth> 0.77"



### Summary for Subcatchment DA-17: Area 17

Runoff = 0.45 cfs @ 12.04 hrs, Volume= 0.028 af, Depth> 0.77"



### Summary for Subcatchment DA-18: Area 18

Runoff = 0.66 cfs @ 12.36 hrs, Volume= 0.089 af, Depth> 0.77"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Type II 24-hr 25yr/24hr NOAA Rainfall=3.93"

	Area	(ac) C	N Dese	cription		
*	1.	400 6	61			
	1.	400	100.	00% Pervi	ous Area	
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
	33.1	300	0.0320	0.15		Sheet Flow, n= 0.240 P2= 2.37"
	2.2	164	0.0320	1.25		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
	35.3	464	Total			

### Subcatchment DA-18: Area 18



### Summary for Subcatchment DA-19: Area 19

Runoff = 2.49 cfs @ 12.02 hrs, Volume= 0.145 af, Depth> 0.77"



### Summary for Subcatchment DA-2: Area 2

Runoff = 3.75 cfs @ 12.00 hrs, Volume= 0.200 af, Depth> 0.77"



### Summary for Subcatchment DA-20: Area 20

Runoff = 1.15 cfs @ 12.35 hrs, Volume= 0.150 af, Depth> 0.77"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Type II 24-hr 25yr/24hr NOAA Rainfall=3.93"

	Area	(ac) <u>C</u>	N Dese	cription		
*	2.	350 6	61			
_	2.	350	100.	00% Pervi	ous Area	
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
	32.2	300	0.0343	0.16		Sheet Flow, n= 0.240 P2= 2.37"
	1.0	78	0.0343	1.30		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
_	33.2	378	Total			

### Subcatchment DA-20: Area 20



### Summary for Subcatchment DA-21: Area 21

Runoff = 0.84 cfs @ 11.96 hrs, Volume= 0.039 af, Depth> 0.78"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Type II 24-hr 25yr/24hr NOAA Rainfall=3.93"

	Area	(ac) C	N Des	cription		
*	0.	600 6	61			
	0.	600	100.	00% Pervi	ous Area	
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
	3.3	54	0.3333	0.27		Sheet Flow, n= 0.240 P2= 2.37"
	0.6	211	0.0280	5.88	23.51	Channel Flow, Area= 4.0 sf Perim= 6.7' r= 0.60' n= 0.030
_	39	265	Total			

### Subcatchment DA-21: Area 21



### Summary for Subcatchment DA-3: Area 3

Runoff = 5.72 cfs @ 12.10 hrs, Volume= 0.445 af, Depth> 0.77"



### Summary for Subcatchment DA-4: Area 4

Runoff = 1.12 cfs @ 12.08 hrs, Volume= 0.081 af, Depth> 0.77"



# Summary for Subcatchment DA-5: Area 5

Runoff = 4.04 cfs @ 12.38 hrs, Volume= 0.560 af, Depth> 0.77"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Type II 24-hr 25yr/24hr NOAA Rainfall=3.93"

	Area	(ac) C	CN Des	cription			
*	8.	780	61				
_	8.	780	100.	00% Pervi	ous Area		
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
	5.3	83	0.2400	0.26		Sheet Flow, n= 0.240 P2= 2.37"	
	29.8	217	0.0217	0.12		Sheet Flow, n= 0.240 P2= 2.37"	
	1.2	74	0.0217	1.03		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps	
	36.3	374	Total				

### Subcatchment DA-5: Area 5



### Summary for Subcatchment DA-6: Area 6

Runoff = 4.26 cfs @ 11.99 hrs, Volume= 0.218 af, Depth> 0.78"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Type II 24-hr 25yr/24hr NOAA Rainfall=3.93"

	Area	(ac) (	CN Des	cription		
*	3.	370	61			
	3.	370	100	.00% Pervi	ious Area	
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
	4.5	78	0.3116	0.29		Sheet Flow, n= 0.240 P2= 2.37"
	1.2	396	0.0252	5.58	22.30	Channel Flow, Area= 4.0 sf Perim= 6.7' r= 0.60' n= 0.030
	0.4	278	0.1007	11.14	44.58	Channel Flow, Area= 4.0 sf Perim= 6.7' r= 0.60' n= 0.030
_	6.1	752	Total			

### Subcatchment DA-6: Area 6



## Summary for Subcatchment DA-7A: Area 7

Runoff = 0.57 cfs @ 12.49 hrs, Volume= 0.091 af, Depth> 0.76"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Type II 24-hr 25yr/24hr NOAA Rainfall=3.93"

	Area	(ac) <u> </u>	N Des	cription		
*	1.	440 6	61			
	1.	440	100.	00% Pervi	ous Area	
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
	40.3	300	0.0196	0.12		Sheet Flow, n= 0.240 P2= 2.37"
	3.6	210	0.0196	0.98		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
	43.9	510	Total			

### Subcatchment DA-7A: Area 7



### Summary for Subcatchment DA-7B: Area 7B

Runoff = 1.13 cfs @ 12.44 hrs, Volume= 0.168 af, Depth> 0.76"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Type II 24-hr 25yr/24hr NOAA Rainfall=3.93"

	Area	(ac) C	<u>N Dese</u>	cription		
*	2.	640 6	61			
	2.	640	100.	00% Pervi	ous Area	
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
	37.6	300	0.0232	0.13		Sheet Flow, n= 0.240 P2= 2.37"
	2.4	151	0.0232	1.07		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
	40.0	451	Total			

### Subcatchment DA-7B: Area 7B



#### Summary for Subcatchment DA-8: Area 8

Runoff = 0.31 cfs @ 11.96 hrs, Volume= 0.014 af, Depth> 0.78"



### Summary for Subcatchment DA-9: Area 9

Runoff = 1.75 cfs @ 12.05 hrs, Volume= 0.115 af, Depth> 0.77"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Type II 24-hr 25yr/24hr NOAA Rainfall=3.93"

	Area	(ac) C	N Dese	cription		
*	1.	790 6	61			
	1.	790	100.	00% Pervi	ous Area	
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
	9.8	126	0.1190	0.21		Sheet Flow, n= 0.240 P2= 2.37"
	1.8	453	0.0141	4.17	16.68	Channel Flow, Area= 4.0 sf Perim= 6.7' r= 0.60' n= 0.030
	11.6	579	Total			

### Subcatchment DA-9: Area 9



### Summary for Pond 34P: Culvert 1

Inflow Are	ea =	10.660 ac,	0.00% Impervious, Inflow	Depth > 0.76" for 25yr/24hr NOAA event
Inflow	=	4.40 cfs @	12.14 hrs, Volume=	0.675 af
Outflow	=	4.40 cfs @	12.14 hrs, Volume=	0.675 af, Atten= 0%, Lag= 0.0 min
Primary	=	4.40 cfs @	12.14 hrs, Volume=	0.675 af
	_			

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Peak Elev= 785.38' @ 12.17 hrs Flood Elev= 790.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	784.35'	<b>24.0" Round Culvert</b> L= 50.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 784.35' / 784.10' S= 0.0050 '/' Cc= 0.900 n= 0.010 PVC, smooth interior

**Primary OutFlow** Max=4.38 cfs @ 12.14 hrs HW=785.38' TW=784.91' (Dynamic Tailwater) **1=Culvert** (Outlet Controls 4.38 cfs @ 3.91 fps)



### Pond 34P: Culvert 1

### Summary for Pond 55P: Culvert #3

Inflow Area = 25.240 ac, 0.00% Impervious, Inflow Depth > 0.75" for 25yr/24hr NOAA event 10.17 cfs @ 12.35 hrs, Volume= 1.588 af Inflow = Outflow 10.17 cfs @ 12.35 hrs, Volume= 1.588 af, Atten= 0%, Lag= 0.0 min = 10.17 cfs @ 12.35 hrs, Volume= 1.588 af Primary = Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Peak Elev= 777.39' @ 12.35 hrs Flood Elev= 782.00' Invert **Outlet Devices** Device Routing 776.00' 36.0" Round Culvert #1 Primary L= 40.0' CMP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 776.00' / 775.00' S= 0.0250 '/' Cc= 0.900 n= 0.025 Corrugated metal

Primary OutFlow Max=10.17 cfs @ 12.35 hrs HW=777.39' TW=775.76' (Dynamic Tailwater) -1=Culvert (Inlet Controls 10.17 cfs @ 3.17 fps)



### Pond 55P: Culvert #3

### Summary for Pond 62P: Culvert No.4

Inflow Area =63.730 ac,0.00% Impervious, Inflow Depth >0.75" for 25yr/24hr NOAA eventInflow =20.74 cfs @12.45 hrs, Volume=4.006 afOutflow =20.74 cfs @12.45 hrs, Volume=4.006 afPrimary =20.74 cfs @12.45 hrs, Volume=4.006 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Peak Elev= 772.19' @ 12.45 hrs

	Device	Routing	Invert	Outlet Devices	
#1 Primary 770.51' <b>30.0" Round Culvert #4 X 2.00</b> L= 24.0' CPP, mitered to conform to fill, Ke= 0.700 Inlet / Outlet Invert= 770.51' / 770.42' S= 0.0038 '/' Cc= 0.900 n= 0.011 Concrete pipe, straight & clean	#1	Primary	770.51'	<b>30.0" Round Culvert #4 X 2.00</b> L= 24.0' CPP, mitered to conform to fill, Ke= 0.700 Inlet / Outlet Invert= 770.51' / 770.42' S= 0.0038 '/' Cc= 0.900 n= 0.011 Concrete pipe, straight & clean	

Primary OutFlow Max=20.74 cfs @ 12.45 hrs HW=772.18' TW=771.45' (Dynamic Tailwater) -1=Culvert #4 (Barrel Controls 20.74 cfs @ 4.20 fps)



### Pond 62P: Culvert No.4



Type II 24-hr 25yr/24hr NOAA Rainfall=3.93"









### Summary for Reach 4R: Downchute 6 Reach 1







Time (hours)





0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 2 Time (hours)






#### Summary for Reach 63R: Channel A Outlet

Inflow Area =63.730 ac, 0.00% Impervious, Inflow Depth > 0.75" for 25yr/24hr NOAA eventInflow =20.74 cfs @12.45 hrs, Volume=4.006 afOutflow =20.15 cfs @12.54 hrs, Volume=3.973 af, Atten= 3%, Lag= 4.9 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Max. Velocity= 2.12 fps, Min. Travel Time= 7.1 min Avg. Velocity = 1.17 fps, Avg. Travel Time= 12.9 min

Peak Storage= 8,593 cf @ 12.54 hrs Average Depth at Peak Storage= 1.04' Bank-Full Depth= 2.00', Capacity at Bank-Full= 72.72 cfs

6.00' x 2.00' deep channel, n= 0.030 Side Slope Z-value= 3.0 '/' Top Width= 18.00' Length= 905.2' Slope= 0.0027 '/' Inlet Invert= 770.42', Outlet Invert= 768.00'



Reach 63R: Channel A Outlet



## Summary for Reach 25R: Channel A Reach 1

Inflow Area =63.730 ac,0.00% Impervious, Inflow Depth >0.76" for 25yr/24hr NOAA eventInflow =20.76 cfs @12.44 hrs, Volume=4.010 afOutflow =20.74 cfs @12.45 hrs, Volume=4.006 af, Atten= 0%, Lag= 0.7 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Max. Velocity= 2.40 fps, Min. Travel Time= 0.9 min Avg. Velocity = 1.30 fps, Avg. Travel Time= 1.7 min

Peak Storage= 1,139 cf @ 12.45 hrs Average Depth at Peak Storage= 0.97' Bank-Full Depth= 2.00', Capacity at Bank-Full= 85.69 cfs

6.00' x 2.00' deep channel, n= 0.030 Side Slope Z-value= 3.0 '/' Top Width= 18.00' Length= 132.0' Slope= 0.0037 '/' Inlet Invert= 771.00', Outlet Invert= 770.51'



Reach 25R: Channel A Reach 1



## Summary for Reach 7R: Channel A, Reach 2

 Inflow Area =
 32.480 ac, 0.00% Impervious, Inflow Depth > 0.76" for 25yr/24hr NOAA event

 Inflow =
 11.83 cfs @ 12.34 hrs, Volume=
 2.051 af

 Outflow =
 11.73 cfs @ 12.38 hrs, Volume=
 2.041 af, Atten= 1%, Lag= 2.5 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Max. Velocity= 2.17 fps, Min. Travel Time= 3.9 min Avg. Velocity = 1.07 fps, Avg. Travel Time= 7.9 min

Peak Storage= 2,757 cf @ 12.38 hrs Average Depth at Peak Storage= 0.73' Bank-Full Depth= 2.00', Capacity at Bank-Full= 75.34 cfs

6.00' x 2.00' deep channel, n= 0.030 Side Slope Z-value= 2.0 '/' Top Width= 14.00' Length= 510.0' Slope= 0.0039 '/' Inlet Invert= 774.00', Outlet Invert= 772.00'



# Reach 7R: Channel A, Reach 2



## Summary for Reach 46R: Channel A, Reach 3

 Inflow Area =
 27.250 ac, 0.00% Impervious, Inflow Depth > 0.76" for 25yr/24hr NOAA event

 Inflow =
 10.65 cfs @ 12.34 hrs, Volume=
 1.717 af

 Outflow =
 10.64 cfs @ 12.36 hrs, Volume=
 1.715 af, Atten= 0%, Lag= 0.9 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Max. Velocity= 2.55 fps, Min. Travel Time= 1.1 min Avg. Velocity = 1.27 fps, Avg. Travel Time= 2.3 min

Peak Storage= 734 cf @ 12.36 hrs Average Depth at Peak Storage= 0.76' Bank-Full Depth= 2.00', Capacity at Bank-Full= 68.81 cfs

4.00' x 2.00' deep channel, n= 0.030 Side Slope Z-value= 2.0 '/' Top Width= 12.00' Length= 176.0' Slope= 0.0057 '/' Inlet Invert= 775.00', Outlet Invert= 774.00'



# Reach 46R: Channel A, Reach 3



## Summary for Reach 45R: Channel A, Reach 4

 Inflow Area =
 25.240 ac,
 0.00% Impervious,
 Inflow Depth >
 0.76"
 for
 25yr/24hr
 NOAA event

 Inflow =
 10.44 cfs @
 12.28 hrs,
 Volume=
 1.599 af

 Outflow =
 10.17 cfs @
 12.35 hrs,
 Volume=
 1.588 af,
 Atten= 3%,
 Lag= 4.2 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Max. Velocity= 2.86 fps, Min. Travel Time= 5.3 min Avg. Velocity = 1.39 fps, Avg. Travel Time= 10.8 min

Peak Storage= 3,203 cf @ 12.35 hrs Average Depth at Peak Storage= 0.67' Bank-Full Depth= 2.00', Capacity at Bank-Full= 82.49 cfs

4.00' x 2.00' deep channel, n= 0.030 Side Slope Z-value= 2.0 '/' Top Width= 12.00' Length= 900.0' Slope= 0.0082 '/' Inlet Invert= 783.35', Outlet Invert= 776.00'



# Reach 45R: Channel A, Reach 4



## Summary for Reach 39R: Channel A, Reach 5

 Inflow Area =
 14.700 ac, 0.00% Impervious, Inflow Depth > 0.76" for 25yr/24hr NOAA event

 Inflow =
 7.39 cfs @
 12.03 hrs, Volume=
 0.935 af

 Outflow =
 5.73 cfs @
 12.18 hrs, Volume=
 0.925 af, Atten= 22%, Lag= 9.4 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Max. Velocity= 1.24 fps, Min. Travel Time= 8.3 min Avg. Velocity = 0.62 fps, Avg. Travel Time= 16.5 min

Peak Storage= 2,838 cf @ 12.18 hrs Average Depth at Peak Storage= 0.82' Bank-Full Depth= 2.00', Capacity at Bank-Full= 31.93 cfs

4.00' x 2.00' deep channel, n= 0.030 Side Slope Z-value= 2.0 '/' Top Width= 12.00' Length= 613.0' Slope= 0.0012 '/' Inlet Invert= 784.10', Outlet Invert= 783.35'





Time (hours)

Type II 24-hr 25yr/24hr NOAA Rainfall=3.93"

## Summary for Reach 33R: Channel A, Reach 7



## Summary for Reach 55R: Channel B, Reach 1

 Inflow Area =
 31.250 ac,
 0.00% Impervious, Inflow Depth >
 0.76" for 25yr/24hr NOAA event

 Inflow =
 12.65 cfs @
 11.94 hrs, Volume=
 1.975 af

 Outflow =
 11.28 cfs @
 11.97 hrs, Volume=
 1.969 af, Atten=

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Max. Velocity= 2.21 fps, Min. Travel Time= 2.7 min Avg. Velocity = 1.18 fps, Avg. Travel Time= 5.0 min

Peak Storage= 1,799 cf @ 11.97 hrs Average Depth at Peak Storage= 0.80' Bank-Full Depth= 2.00', Capacity at Bank-Full= 73.08 cfs

4.00' x 2.00' deep channel, n= 0.030 Side Slope Z-value= 3.0 '/' Top Width= 16.00' Length= 352.0' Slope= 0.0043 '/' Inlet Invert= 773.50', Outlet Invert= 772.00'



## Reach 55R: Channel B, Reach 1



#### Summary for Reach 51R: Channel B, Reach 2

0.00% Impervious, Inflow Depth > 0.76" for 25yr/24hr NOAA event Inflow Area = 14.100 ac, 4.79 cfs @ 12.36 hrs, Volume= Inflow 0.892 af = 4.55 cfs @ 12.48 hrs, Volume= 0.881 af, Atten= 5%, Lag= 7.1 min Outflow = Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Max. Velocity= 1.81 fps, Min. Travel Time= 9.8 min Avg. Velocity = 0.96 fps, Avg. Travel Time= 18.5 min Peak Storage= 2,672 cf @ 12.48 hrs Average Depth at Peak Storage= 0.47' Bank-Full Depth= 2.00', Capacity at Bank-Full= 80.53 cfs 4.00' x 2.00' deep channel, n= 0.030 Side Slope Z-value= 3.0 '/' Top Width= 16.00' Length= 1,063.0' Slope= 0.0052 '/' Inlet Invert= 779.00', Outlet Invert= 773.50' ‡ Reach 51R: Channel B, Reach 2 Hydrograph Inflow Outflow Inflow Area=14.100 ac 5 Avg. Flow Depth=0.47 Max Vel=1.81 fps 4 n=0.030 L=1,063.0' Flow (cfs) S=0.0052 '/' 2 Capacity=80.53 cfs 1 0 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24

Time (hours)

#### Summary for Reach 56R: Channel B, Reach 3

6.920 ac, 0.00% Impervious, Inflow Depth > 0.77" for 25yr/24hr NOAA event Inflow Area = 5.72 cfs @ 12.10 hrs, Volume= 0.445 af Inflow = 3.04 cfs @ 12.26 hrs, Volume= 0.434 af, Atten= 47%, Lag= 9.7 min Outflow = Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Max. Velocity= 1.54 fps, Min. Travel Time= 18.8 min Avg. Velocity = 0.71 fps, Avg. Travel Time= 40.4 min Peak Storage= 3,424 cf @ 12.26 hrs Average Depth at Peak Storage= 0.38' Bank-Full Depth= 2.00', Capacity at Bank-Full= 76.13 cfs 4.00' x 2.00' deep channel, n= 0.030 Side Slope Z-value= 3.0 '/' Top Width= 16.00' Length= 1,730.0' Slope= 0.0046 '/' Inlet Invert= 787.00', Outlet Invert= 779.00' ‡ Reach 56R: Channel B, Reach 3 Hydrograph Inflow Outflow Inflow Area=6.920 ac Avg. Flow Depth=0.38' 5 Max Vel=1.54 fps n=0.030 Flow (cfs) L=1,730.0' 3.04 cf S=0.0046 '/' Capacity=76.13 cfs 2-1 0 10 11 12 13 14 15 16 Time (hours) 2 6 7 8 9 17 18 19 20 21 22 23 24

#### Summary for Reach 64R: Channel C

 Inflow Area =
 2.770 ac, 0.00% Impervious, Inflow Depth > 0.78" for 25yr/24hr NOAA event

 Inflow =
 4.18 cfs @
 11.94 hrs, Volume=
 0.179 af

 Outflow =
 2.83 cfs @
 11.99 hrs, Volume=
 0.177 af, Atten= 32%, Lag= 3.1 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Max. Velocity= 4.10 fps, Min. Travel Time= 6.5 min Avg. Velocity = 1.38 fps, Avg. Travel Time= 19.2 min

Peak Storage= 1,098 cf @ 11.99 hrs Average Depth at Peak Storage= 0.27' Bank-Full Depth= 1.00', Capacity at Bank-Full= 33.23 cfs

2.00' x 1.00' deep channel, n= 0.030 Side Slope Z-value= 2.0 '/' Top Width= 6.00' Length= 1,591.0' Slope= 0.0534 '/' Inlet Invert= 884.00', Outlet Invert= 799.00'



#### Summary for Reach 65R: Channel E

0.00% Impervious, Inflow Depth > 0.78" for 25yr/24hr NOAA event 1.660 ac, Inflow Area = 2.22 cfs @ 11.97 hrs, Volume= Inflow 0.107 af = 1.58 cfs @ 12.03 hrs, Volume= 0.106 af, Atten= 29%, Lag= 3.2 min Outflow = Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Max. Velocity= 2.02 fps, Min. Travel Time= 6.6 min Avg. Velocity = 0.65 fps, Avg. Travel Time= 20.3 min Peak Storage= 624 cf @ 12.03 hrs Average Depth at Peak Storage= 0.17' Bank-Full Depth= 1.00', Capacity at Bank-Full= 37.94 cfs 4.00' x 1.00' deep channel, n= 0.030 Side Slope Z-value= 3.0 '/' Top Width= 10.00' Length= 796.0' Slope= 0.0201 '/' Inlet Invert= 832.00', Outlet Invert= 816.00' ‡ Reach 65R: Channel E Hydrograph Inflow Outflow 2.22 cf Inflow Area=1.660 ac Avg. Flow Depth=0.17' 2 Max Vel=2.02 fps 1.58 n=0.030 Flow (cfs) L=796.0' S=0.0201 '/' Capacity=37.94 cfs 0 ź à 5 Ŕ ġ 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 3 8 Time (hours)

## Summary for Reach 68R: Channel F Reach 1

 Inflow Area =
 3.370 ac, 0.00% Impervious, Inflow Depth > 0.78" for 25yr/24hr NOAA event

 Inflow =
 4.26 cfs @
 11.99 hrs, Volume=
 0.218 af

 Outflow =
 3.96 cfs @
 12.01 hrs, Volume=
 0.217 af, Atten= 7%, Lag= 1.5 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Max. Velocity= 3.15 fps, Min. Travel Time= 2.5 min Avg. Velocity = 0.97 fps, Avg. Travel Time= 8.0 min

Peak Storage= 584 cf @ 12.01 hrs Average Depth at Peak Storage= 0.26' Bank-Full Depth= 1.00', Capacity at Bank-Full= 46.43 cfs

4.00' x 1.00' deep channel, n= 0.030 Side Slope Z-value= 3.0 '/' Top Width= 10.00' Length= 465.0' Slope= 0.0301 '/' Inlet Invert= 832.00', Outlet Invert= 818.00'



#### Summary for Reach 69R: Channel F Reach 2

0.00% Impervious, Inflow Depth > 0.77" for 25yr/24hr NOAA event Inflow Area = 3.370 ac, 3.96 cfs @ 12.01 hrs, Volume= 0.217 af Inflow = 0.217 af, Atten= 0%, Lag= 0.2 min 3.96 cfs @ 12.02 hrs, Volume= Outflow Ξ Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Max. Velocity= 9.76 fps, Min. Travel Time= 0.2 min Avg. Velocity = 2.94 fps, Avg. Travel Time= 0.8 min Peak Storage= 54 cf @ 12.02 hrs Average Depth at Peak Storage= 0.15' Bank-Full Depth= 1.00', Capacity at Bank-Full= 128.63 cfs 2.50' x 1.00' deep channel, n= 0.015 Side Slope Z-value= 2.0 '/' Top Width= 6.50' Length= 134.0' Slope= 0.1493 '/' Inlet Invert= 818.00', Outlet Invert= 798.00' Reach 69R: Channel F Reach 2 Hydrograph Inflow Outflow Inflow Area=3.370 a Avg. Flow Depth=0.1 Max Vel=9.76 fps 3. n=0.015 Flow (cfs) L=134.0' S=0.1493 '/' 2 Capacity=128.63 cfs 1 3 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 Time (hours)



#### Summary for Reach 22R: Clean water diversion ditch

Inflow Area =52.858 ac,0.00% Impervious,Inflow Depth >0.77" for 25yr/24hr NOAA eventInflow =41.97 cfs @12.11 hrs,Volume=3.389 afOutflow =41.68 cfs @12.13 hrs,Volume=3.384 af,Atten= 1%,Lag= 0.8 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Max. Velocity= 7.69 fps, Min. Travel Time= 1.1 min Avg. Velocity = 3.39 fps, Avg. Travel Time= 2.4 min

Peak Storage= 2,658 cf @ 12.13 hrs Average Depth at Peak Storage= 1.22' Bank-Full Depth= 3.00', Capacity at Bank-Full= 306.69 cfs

2.00' x 3.00' deep channel, n= 0.010 Side Slope Z-value= 2.0 '/' Top Width= 14.00' Length= 490.4' Slope= 0.0041 '/' Inlet Invert= 777.00', Outlet Invert= 774.99'

## Reach 22R: Clean water diversion ditch



#### Summary for Reach 29R: Clean water diversion ditch

Inflow Area = 55.168 ac, 0.00% Impervious, Inflow Depth > 0.77" for 25yr/24hr NOAA event Inflow = 43.47 cfs @ 12.12 hrs, Volume= 3.533 afOutflow = 42.44 cfs @ 12.15 hrs, Volume= 3.524 af, Atten= 2%, Lag= 1.6 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Max. Velocity= 5.67 fps, Min. Travel Time= 2.0 min Avg. Velocity = 2.57 fps, Avg. Travel Time= 4.3 min

Peak Storage= 5,002 cf @ 12.15 hrs Average Depth at Peak Storage= 1.50' Bank-Full Depth= 3.00', Capacity at Bank-Full= 202.13 cfs

2.00' x 3.00' deep channel, n= 0.010 PVC, smooth interior Side Slope Z-value= 2.0 '/' Top Width= 14.00' Length= 668.4' Slope= 0.0018 '/' Inlet Invert= 774.99', Outlet Invert= 773.80'



## Reach 29R: Clean water diversion ditch



#### Summary for Reach 31R: Clean water diversion ditch

 Inflow Area =
 63.278 ac,
 0.00% Impervious, Inflow Depth >
 0.77" for 25yr/24hr NOAA event

 Inflow =
 48.63 cfs @
 12.15 hrs, Volume=
 4.046 af

 Outflow =
 41.43 cfs @
 12.22 hrs, Volume=
 4.018 af, Atten= 15%, Lag= 4.5 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Max. Velocity= 4.33 fps, Min. Travel Time= 5.7 min Avg. Velocity = 2.09 fps, Avg. Travel Time= 11.9 min

Peak Storage= 14,213 cf @ 12.22 hrs Average Depth at Peak Storage= 1.74' Bank-Full Depth= 3.00', Capacity at Bank-Full= 141.74 cfs

2.00' x 3.00' deep channel, n= 0.010 Side Slope Z-value= 2.0 '/' Top Width= 14.00' Length= 1,485.0' Slope= 0.0009 '/' Inlet Invert= 773.80', Outlet Invert= 772.50'



## Reach 31R: Clean water diversion ditch



## Summary for Reach 21R: Clean water diversion ditch

Inflow Area =52.280 ac,0.00% Impervious, Inflow Depth >0.77" for 25yr/24hr NOAA eventInflow =45.53 cfs @12.07 hrs, Volume=3.368 afOutflow =41.84 cfs @12.11 hrs, Volume=3.352 af, Atten= 8%, Lag= 2.7 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Max. Velocity= 5.09 fps, Min. Travel Time= 3.6 min Avg. Velocity = 2.30 fps, Avg. Travel Time= 8.1 min

Peak Storage= 9,145 cf @ 12.11 hrs Average Depth at Peak Storage= 1.59' Bank-Full Depth= 3.00', Capacity at Bank-Full= 175.83 cfs

2.00' x 3.00' deep channel, n= 0.010 PVC, smooth interior Side Slope Z-value= 2.0 '/' Top Width= 14.00' Length= 1,113.5' Slope= 0.0013 '/' Inlet Invert= 778.50', Outlet Invert= 777.00'



## Reach 21R: Clean water diversion ditch









#### Summary for Reach 10R: North Berm Channel 1 Stage 5

Inflow Area =8.780 ac, 0.00% Impervious, Inflow Depth > 0.77" for 25yr/24hr NOAA eventInflow =4.04 cfs @12.38 hrs, Volume=0.560 afOutflow =3.70 cfs @12.50 hrs, Volume=0.553 af, Atten= 8%, Lag= 7.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Max. Velocity= 2.03 fps, Min. Travel Time= 8.6 min Avg. Velocity = 0.92 fps, Avg. Travel Time= 19.0 min

Peak Storage= 1,915 cf @ 12.50 hrs Average Depth at Peak Storage= 0.31' Bank-Full Depth= 1.00', Capacity at Bank-Full= 31.43 cfs

5.00' x 1.00' deep channel, n= 0.030 Side Slope Z-value= 3.0 '/' Top Width= 11.00' Length= 1,050.0' Slope= 0.0100 '/' Inlet Invert= 808.00', Outlet Invert= 797.50'



## Reach 10R: North Berm Channel 1 Stage 5



#### Summary for Reach 16R: Junction

Inflow Area =67.318 ac,0.00% Impervious, Inflow Depth >0.76" for 25yr/24hr NOAA eventInflow =42.94 cfs @12.22 hrs, Volume=4.278 afOutflow =42.94 cfs @12.22 hrs, Volume=4.278 af, Atten= 0%, Lag= 0.1 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Max. Velocity= 17.37 fps, Min. Travel Time= 0.1 min Avg. Velocity = 6.92 fps, Avg. Travel Time= 0.2 min

Peak Storage= 238 cf @ 12.22 hrs Average Depth at Peak Storage= 0.50' Bank-Full Depth= 2.00', Capacity at Bank-Full= 591.65 cfs

4.00' x 2.00' deep channel, n= 0.010 Side Slope Z-value= 2.0 '/' Top Width= 12.00' Length= 96.4' Slope= 0.0467 '/' Inlet Invert= 772.50', Outlet Invert= 768.00'



Reach 16R: Junction



#### Summary for Reach 5R: South Berm Channel, Reach 2

Page 44

0.00% Impervious, Inflow Depth > 0.77" for 25yr/24hr NOAA event Inflow Area = 2.240 ac, 2.49 cfs @ 12.02 hrs, Volume= 0.145 af Inflow = 1.24 cfs @ 12.13 hrs, Volume= 0.141 af, Atten= 50%, Lag= 6.4 min Outflow =

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Max. Velocity= 1.12 fps, Min. Travel Time= 15.4 min Avg. Velocity = 0.43 fps, Avg. Travel Time= 40.0 min

Peak Storage= 1,152 cf @ 12.13 hrs Average Depth at Peak Storage= 0.11' Bank-Full Depth= 1.00', Capacity at Bank-Full= 50.55 cfs

9.50' x 1.00' deep channel, n= 0.030 Side Slope Z-value= 3.0 2.0 '/' Top Width= 14.50' Length= 1,036.0' Slope= 0.0097 '/' Inlet Invert= 815.00', Outlet Invert= 805.00'





#### Summary for Pond 11P: Designed Sed Pond

Inflow Area	=	133.348 ac,	0.00% Impervious,	Inflow Depth >	0.75" for	25yr/24hr NOAA event
Inflow	=	57.25 cfs @	12.23 hrs, Volume	= 8.386 a	af	
Outflow	=	7.36 cfs @	15.35 hrs, Volume	= 5.438 a	af, Atte <mark>n=</mark> 8	37%, Lag= 187.0 min
Primary	=	7.36 cfs @	15.35 hrs, Volume	= 5.438 a	af	
Secondary	=	0.00 cfs @	0.00 hrs, Volume	= 0.000 a	af	

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Peak Elev= 763.35' @ 15.35 hrs Surf.Area= 2.964 ac Storage= 3.932 af

Plug-Flow detention time= 285.0 min calculated for 5.438 af (65% of inflow) Center-of-Mass det. time= 158.0 min (1,071.7 - 913.7)

Volume	Invert A	vail.Stora	ge Stora	age Description				
#1	762.00'	18.485	af <b>Sed</b>	Pond (Prismatic) Listed below (Recalc)				
Elevation Surf.Area		Inc.Store		Cum.Store				
(feet) (acres)		(acr						
762.0	0 2.870		0.000	0.000				
763.0	0 2.940		2.905	2.905				
764.0	0 3.010		2.975	5.880				
765.0	0 3.080		3.045	8.925				
766.0	0 3.150		3.115	12.040				
767.0	0 3.220		3.185	15.225				
768.0	0 3.300		3.260	18.485				
Device	Routing	Invert	Outlet De	levices				
#1	Primary	762.00'	24.0" Ro	ound Barrel				
	-		L= 50.0'	RCP, mitered to conform to fill, Ke= 0.700				
			Inlet / Ou	utlet Invert= 762.00' / 761.50' S= 0.0100 '/' Cc= 0.900				
			n= 0.015	5				
#2	#2 Device 1		6.0" Vert	rt. Perf Riser X 8.00 columns				
			X 3 rows	s with 6.0" cc spacing C= 0.600				
#3	#3 Device 1		<b>24.0" Horiz. Top of Riser</b> $C = 0.600$					
			Limited t	to weir flow at low heads				
#4	Secondary	765.40'	Emerger	ncy Spillway, Cv= 2.62 (C= 3.28)				
	-		Head (fe	eet) 0.00 0.60				
			Width (fe	eet) 100.00 102.40				
Primary	Primary OutFlow Max=7.36 cfs @ 15.35 hrs HW=763.35' (Free Discharge)							

-1=Barrel (Barrel Controls 7.36 cfs @ 4.62 fps)

**2=Perf Riser** (Passes 7.36 cfs of 8.19 cfs potential flow)

-3=Top of Riser (Controls 0.00 cfs)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=762.00' (Free Discharge) 4=Emergency Spillway (Controls 0.00 cfs)



# Pond 11P: Designed Sed Pond